

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-065-20718-00-00

LEASE NAME Fountain

TYPE OR PRINT

WELL NUMBER W2

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

4950 Ft. from S Section Line

2310 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc.

SEC. 5 TWP. 9S RGE. 23W (E) or (W)

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

COUNTY Graham

PHONE # () 267-3241 OPERATORS LICENSE NO. 30606

Date Well Completed 3/30

Character of Well INJ (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging commenced 11/06/95

Plugging Completed 11/07/95

The plugging proposal was approved on _____ (date)
by _____ (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ TD _____

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put | Pulled out |
|-----------|---------|------|----|-------|------|------------|
| | | | | 7 | 120 | |
| | | | | 3 1/2 | 3897 | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Perforated 3 1/2" csg @ 1170' & 225'. RIH w/1 1/2" tbg to 1210'. Pumped 68 sx 60/40 Poz, 10% gel dwn tbg to circ cmt to surface.

TOH w/tbg. Tied onto 3 1/2" csg, pumped 48 sx 60/40 Poz, 10% gel. Max press 150 psig. ISIP 100 psig. Tied onto 7" csg. Pumped

100 sx 60/40 Poz, 10% gel, 100# hulls. Max press 200 psig. ISIP 100 psig. JC 12 p.m. 11/7 Cement to surface. Cut off & capped.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606

Address 250 N. Water, Suite 300; Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK

Larry M. Jack, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Larry M. Jack
(Address) Wichita, KS



SUBSCRIBED AND SWORN TO before me this 13 day of Nov., 1995

Kerran Redington
Notary Public - Kerran Redington

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1995
11-15-95
WICHITA, KANSAS