

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 9/20/67

LEASE NAME Stewart

WELL NUMBER #2 SWD

SPOT LOCATION C NE NW

SEC. 8 TWP. 9 RGE. 23 ~~W~~ W

COUNTY Graham

Date Well Completed 9/20/67

Plugging Commenced 2/5/86

Plugging Completed 2/5/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Beren Corporation

ADDRESS 970 Fourth Financial Center, Wichita, KS 67202

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5364

Character of Well SWD FOR KCCAP
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? District 6, Hays

Is ACO-1 filed? NO If not, is well log attached? YES

Producing formation Topeka & KC Depth to top 3425' 3620' bottom 3578' 3840' T.D. 3862'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	258'	None
				4 1/2"	3860'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pump 130 sx 60/40 poz cmt with 6% gel, 3% cc & 1 1/2 sx celloseal down 4 1/2" csg. Pump 5 sx of same cmt blend down 4 1/2"-8 5/8" annulus.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Beren Corporation License No. 5364

Address 970 Fourth Financial Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.


Evan C. Mayhew (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Evan C Mayhew

(Address) 970 Fourth Financial Center

SUBSCRIBED AND SWORN TO before me this 24 day of March, 19 86

Cecilia A. Bowser
Notary Public



My Commission expires: August 5, 1987

STATE CORPORATION COMMISSION

MAR 25 1986
3-25-86
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4 /-S
Revised 06-83

AMERADA PETROLEUM CORP.

COMPANY
CONTRACTOR
FARM
LOCATION

EXHIBIT D-2
NO. _____
DATE _____

Amerada Petroleum Corporation
LEBEN DRILLING, INC.
H H STEWART #2
C NE NW Section 8-9s-23w
Graham County, Kansas
9-8-67
9-20-67

COMMENCED
COMPLETED

0	1680	Shale
1680	1928	Red Bed
1928	1968	Anhydrite
1968	3037	Shale
3037	3452	Shale and Lime
3452	3644	Lime and Shale
3644	3728	Lime
3728	3794	Lime and Chert
3794	3862	Lime
	3862	RTD - Set 4½" Casing

8 5/8" New Surface Casing - Set @ 258' with 175 sx Common Cement ¼# Flo-seal
2% cc - Cement Circulated

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the H. H. Stewart #2, located C NE NW of Section 8, Township 9 South, Range 23 West, Graham County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite
LESLIE KITE

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 22nd day of September, 1967.

Ulanda Nichols
Ulanda Nichols, Notary Public

My Commission Expires: April 1, 1971

RECEIVED
STATE CORPORATION COMMISSION

MAR 25 1967

CONSERVATION DIVISION
Wichita, Kansas