

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 10/11/65

LEASE NAME Stewart

WELL NUMBER #1

SPOT LOCATION C NW NW

SEC. 8 TWP. 9 RGE. 23 (E or W)

COUNTY Graham

Date Well Completed 10/11/65

Plugging Commenced 2/5/86

Plugging Completed 2/5/86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Beren Corporation

ADDRESS 970 Fourth Financial Center, Wichita, KS 67202

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5364

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? District 6, Hays

Is ACO-1 filed? NO If not, is well log attached? YES

Producing formation LKC Depth to top 3690' bottom 3875' T.D. 3925'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	250'	None
				4 1/2"	3922'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pump 150 sx 60/40 pozmix cmt down 8 5/8"-4 1/2" annulus.  
Pump down 4 1/2" csg as follows: 50 sx 60/40 poz cmt,  
1 sx hulls, 50 sx 60/40 poz cmt, 6 sx gel, 10 sx 60/40 poz  
All 60/40 poz containing 6% gel 3% cc  
(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Beren Corporation License No. 5364

Address 970 Fourth Financial Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Evan C. Mayhew (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) Evan C Mayhew  
(Address) 970 Fourth Financial Center



SUBSCRIBED AND SWORN TO before me this 24 day of March, 1986

Cecelia A. Bowser  
Notary Public

My Commission expires: August 5, 1987

RECEIVED  
STATE CORPORATION COMMISSION  
3-25-86  
**MAR 25 1986**

Form CP-4 1-5  
Revised 06-83

DRILLER'S LOG

COMPANY:  
CONTRACTOR:  
FARM:  
LOCATION:  
  
COMMENCED:  
COMPLETED:

Amerada Petroleum Company  
LEBEN DRILLING, INC.  
STEWART #1  
C NW NW Sec. 8-9S-23W  
GRAHAM COUNTY, KANSAS  
10-1-65  
10-11-65

0	250	Surface soil
250	960	Shale
960	1223	Sand, shale
1223	1715	Dakota sand, shale
1715	1999	Shale, shells
1999	2035	Anhydrite
2035	2615	Shale, shells
2615	3078	Shale, lime
3078	3230	Lime, shale
3230	3545	Shale, lime
3545	3660	Lime, shale
3660	3773	Lime
3773	3807	Lime, shale
3807	3925	Lime
	<u>3925</u>	<u>RTD - Set 4 1/2" Casing</u>

Set 8 5/8" 24# new surface casing @ 250' with 175 sacks Common cement, last 100 sacks 2% ce

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Stewart #1 well, located C NW NW of Section 8, Township 9 South, Range 23 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

*Leslie Kite*

Leslie Kite

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 15th day of October, 1965.

*Ulanda Nichols*

Ulanda Nichols

My Commission Expires  
April 1, 1967

RECEIVED  
STATE CORPORATION COMMISSION

MAR 25 1986

CONSERVATION DIVISION  
Wichita, Kansas