


15-065-01001-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 8 Twp. 9S Rge. 23W(E) (W)
Location as "NE/CNW%SW%" or footage from lines NW NW SE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Frazier Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed February 23, 19 57
Application for plugging filed April 17, 19 58
Application for plugging approved April 17, 19 58
Plugging commenced April 29, 19 58
Plugging completed April 29, 19 58
Reason for abandonment of well or producing formation No production.

If a producing well is abandoned, date of last production December, 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius, Hill City, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3920 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand to 3610', dumped 4 sacks cement,
mud to 200', set rock bridge with 15
sacks cement, mud to 35' set rock
bridge with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAY 6 1958
5-6-58
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address P. O. Box 364, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of ~~owner~~ owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Ray L. Bacon -P


780 Fourth National Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of May, 19 58

Louetta M. Duncan
Louetta M. Duncan

Notary Public.

December 19, 1960



PLUGGING
FILE SEC 8 T 9 R 234
BOOK PAGE 94 LINE 5

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
903 Union National Building
Wichita, Kansas

Frazier No. 1
NW NW SE Sec. 8-9S-23W
Graham County, Kansas

Total Depth: 3920'

Commenced: 2-3-57 Completed 2-23-57

Elevation: 2352'

Production: 28 BOPD, no water

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 181' with 150 sacks cement.

Figures indicate bottom of formations:

Sand & Clay	35'		
Shale & Shells	715'		
Sand & Shale	1120'	<u>TOPS</u>	
Sand	1240'	Anhydrite	1995' (✓ 357)
Shale & Sand	1525'	Heebner	3648' {-1296}
Sand	1625'	Lansing	3690' {-1338}
Sand & Shale	1730'	Total Depth	3920' {-1568}
Shale & Red Bed	1995'		
Anhydrite	2030'		
Shale & Shells	2535'		
Shale & Lime	3535'		
Lime	3920'		
Total Depth	3920'		

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: Ray L. Bacon
Vice-President

Subscribed and sworn to before me this 26th day of February, 1957.

My Commission Expires:

December 19, 1960

RECEIVED
STATE COMMISSION

MAY 6 1958

CONSERVATION DIVISION
Wichita, Kansas

Lucretia M. Duncan
Notary Public

PLUGGING
FILE SEC. 8 T. 9 R. 23
BOOK PAGE 941 5