


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 8 Twp. 9 Rge. 23W (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE NW NE  
Lease Owner Chief Drilling Co., Inc.  
Lease Name Engleman Well No. #1  
Office Address Suite 905 Century Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed June 1, 1971 19  
Application for plugging filed June 1, 1971 19  
Application for plugging approved June 1, 1971 19  
Plugging commenced June 1, 1971 19  
Plugging completed June 1, 1971 19  
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3840' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	257.28'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged through drill pipe @ 1025' w/100 sacks cement  
Plugged through drill pipe @ 275' w/25 sacks cement.  
Plugged through drill pipe @ 40' w/10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
6-2-71  
JUN 2 1971  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Chief Drilling Co., Inc.  
Address Suite 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
V. Richard Hoover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover  
Suite 905 Century Plaza, Wichita, Kansas  
(Address)

SWORN TO before me this 1st day of June, 19 71

February 16, 1974  
Karen E. Duarte Notary Public.



8-9-23W

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 4 1971  
CONSERVATION DIVISION  
Wichita, Kansas

WELL LOG

CHIEF DRILLING CO., INC.  
Suite 905 Century Plaza  
Wichita, Kansas 67202

#L ENGLEMAN  
NE NW NE Sec. 8-9-23W  
Graham County, Kansas

CONTRACTOR: Company tools  
CASING RECORD: Set 257.28' of 8 5/8"  
w/175 sacks 60/40 Pozmix

COMMENCED: 5/25/71  
COMPLETED: 6/1/71

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand & shale	0	1035	2283 Gr.
Sand, red bed & shale	1035	1765	2285 D.F.
Shale & shells	1765	1952	2288 K.B.
Anhydrite	1952	1986	
Shale & shells	1986	2150	
Red bed & shale	2150	2600	
Shale & lime	2600	3750	
Lime	3750	3830	
Total depth	3840		

<u>FORMATION TOPS</u>	
Anhydrite	1952 + 336
Base Anhy.	1986 + 302
Heebner	3605 -1317
Toronto	3630 -1342
Lansing	3645 -1357
T. D.	3840 -1552

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NW NW NE of Section 8-9-23W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*Jim Robinson*  
Jim Robinson, Office Manager

Subscribed and sworn to before me this 3rd day of June, 1971.

*Karen E. Duarte*  
Karen E. Duarte, Notary Public

