

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1970  
CONSERVATION DIVISION  
Wichita, Kansas

12-10-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20320-00-01

Operator's Full Name Don Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Sandlin Well No. 1

Location SE-NW-NW Sec. 5 Twp. 10 Rge. (E) (W)22

County Graham Total Depth 3855'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Forbes Casing Pulling Company, Incorporated,

Address Box # 211, Great Bend, Kansas. License No. 637

Operation Completed: Hour 11:15 AM Day 8 Month 12 Year 1970

The above well was plugged as follows:

202'--8 5/8" Surface casing, cement circulated with 185 Sx.  
3854'--4 1/2" Production casing cemented on bottom with 125 Sx. Top of cement @ 3295'  
(Temp. Survey). Well plugged back to 3813'. Top perforations @ 3630'.

Pushed plug to 3600', sanded back to 3575' and set 4 Sx. cement with dump bailer.

Pulled 4 1/2" casing (1302') and squeezed w ell initially with 5 sacks hulls and 15  
sacks gel and followed with 100 Sx. cement from 1025' to 700' then 12 sacks gel from  
700' to 225' and followed with 25 Sx. cement from 225' to 150' then 3 sacks gel from  
150' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum Pump-in  
pressure--300#. Final shut-in pressure-200#. (Mudding and cementing by Allied).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: K. L. Nichols  
Well Plugging Supervisor

DATE 12/10/70

INV. NO. 3037-U