

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20320-00-00

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Sandlin Well-No. 1

Location SE-NW-NW Sec. 5 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 3844'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 10:30 AM Day 19 Month 4 Year 1970

The above well was plugged as follows:

202'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 100 Sx. cement thru
DP from 1025' to 700'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1970
CONSERVATION DIVISION
Wichita, Kansas

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 4/22/70
INV. NO. 1790-W

04-22-1970