

15-065-20709-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1974
09-27-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Barnett Oil, Incorporated & H. Rosen,

Complete Address 411 First National Bank Building, Wichita, Kansas.

Lease Name Griffith Well No. 1

Location CN/2-NE-SW Sec. 5 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 4006'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kans. License No.

Operation Completed: Hour 11:00 PM Day 21 Month 9 Year 1974

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 110 Cu. Ft. cement
thru DP from 950' to 625'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 9/27/74
INV. NO. 9963-W