

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

JUL 18 1966  
07-18-1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

15-065-30150-0000

Operator's Full Name Nadel & Gussman,

Complete Address: 625 Union Center Building, Wichita, Kansas.

Lease Name Rathbun Well No. 3

Location N $\frac{1}{2}$ -S $\frac{1}{2}$ -NE $\frac{1}{4}$  Sec. 34 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3435

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: D & D Drilling Company, Incorporated,

Address: 307 Schweiter Building, Wichita, Kansas. License No.     

Operation Completed: Hour 6:15AM Day 15 Month 7 Year 1966

The Above well was plugged as follows:

184'--8 5/8" Surface pipe, cement circulated with 170 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 180', set plug with  $\frac{1}{2}$  sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with  $\frac{1}{2}$  sack

hulls and 10 Sx. cement to bottom of cellar.

( Cementing operations performed by Halliburton Company )

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Fickel  
Well Plugging Supervisor

DATE 7/18/66  
INV. NO. 3579-4