

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20576-00-00

RECEIVED
STATE CORPORATION COMMISSION
11-09-1972
NOV 9 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Kansas Petroleum, Incorporated,

Complete Address 1620 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Lewis Well No. 1

Location NW-SE-SE Sec. 34 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3473'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 1:30 PM Day 7 Month 11 Year 1972

The above well was plugged as follows:

261'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 650'.

Circulated hole with heavy mud. Pulled DP to 875' and displaced 110 Cu. Ft. cement
thru DP from 875' to 550'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: R. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 11/9/72

INV. NO. 6603-W