

KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1970
CONSERVATION DIVISION
Wichita, Kansas
02-05-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20302-00-00

Operator's Full Name Quintin Little,

Complete Address Box #1509, Ardmore, Oklahoma.

Lease Name Holmquist & Holmes Well No. 1

Location SW-SE-SW Sec. 12 Twp. 10 Rge. (E) (W) 22

County Graham Total Depth 4000'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 10:00 PM Day 1 Month 2 Year 1970

The above well was plugged as follows:

202'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 110 Sx. cement thru
DP from 925' to 565'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. L. Dehols
Well Plugging Supervisor

DATE 2/6/70
INV. NO. 1375-W