

R

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 6 - 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
07-06-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20381-00-00

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Dussault Well No. 1

Location NE-NE-NE Sec. 10 Twp. 10 Rge. (E) (W) 22

County Grāham Total Depth 3815'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling, Incorporated,

Address Box #364, Great Bend, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 12:15 PM Day 29 Month 6 Year 1971

The above well was plugged as follows:

212--8 5/8" Surface casing, cement circulated with 150 Sx.

3814'--5 1/2" Production casing cemented on bottom with 75 Sx. Well plugged back to 3782'. Top perforations from 3736' to 3742'.

Sanded well back to 3725' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (3200') and squeezed well initially with 5 sacks hulls and 12 sacks gel and followed with 105 Sx. cement from 940' to 600' then 9 sacks gel from 600' to 240' and followed with 20 Sx. cement from 240' to 180', then 4 sacks gel from 180' to 20' and finally 10 Sx. cement from 20' to bottom of cellar. Maximum pump-in pressure--250#. Final shut-in pressure--150#. (Mudding and cementing by Halliburton Services).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dickels  
Well Plugging Supervisor

DATE 7-7-71  
INV. NO. 3937-W