


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 11 Twp. 9 Rge 23 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NW NE
Lease Owner Don E. Pratt Oil Operations
Lease Name C. Jones #2 Well No. _____
Office Address Hays, Kansas 67601
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/4/71 19____
Plugging completed 6/17/71 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3850 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	164	none
				4 1/2"	3864'	1834'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 3775', dumped 3 sacks of cement. Loaded hole, shot pipe at 2738', 2645', 2552', 2461', 2368', 2274', 2182', 2089', 1995', 1904', 1808', worked pipe loose and pulled 30 joints. Ran into yellow wrap. Pulled balance of pipe. Pumped 5 sacks hulls, 25 sacks mud and 135 sacks 6% pozmix.


PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1971
CONSERVATION DIVISION
Wichita, Kansas
6-24-71

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)



Subscribed and sworn to before me this 21st day of June, 19 71
Margaret Melcher
Notary Public.

E. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

WELL LOG

Company	Don E. Pratt Oil Operations Box 390 Hays, Kansas 67601	Sec. 11	Twp. 9	Rng. 23
Farm	C. Jones No. 2	Location	SW NW NE	
Total Depth	3850'	County	Graham	
Comm.	9-13-68 Comp. 9-20-68	Elevation:	2320'	K. B.
Contractor	L. J. Dreiling & Sons, Inc. Victoria, Kansas 67671		2317'	D. F.
			2315'	G. R.
		Production:	Temporarily Abandoned	
	Casing Record 164' - 8 5/8"	Cement Record	140 sacks cement	

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1971
CONSERVATION DIVISION
Wichita, Kansas

Figures Indicate Bottom of Formations

0'	40'	Surface Soil
40'	110'	Yellow Clay & Post Rock
110'	164'	Blue Shale
164'	594'	Shale & Shells
594'	952'	Shale
952'	1070'	Dakota Sand
1070'	1490'	Shale
1490'	1735'	Sand
1735'	1949'	Shale & Redbed
1949'	1981'	Anhy.
1981'	2235'	Shale & Lime Streaks
2235'	2605'	Shale & Lime Shell
2605'	2812'	Shale & Lime Streaks
2812'	3090'	Shale & Lime
3090'	3394'	Lime
3394'	3515'	Lime & Shale
3515'	3850'	Lime
3850'	T.D.	

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your C. Jones #2.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 24th day of September 1968.



Joseph A. Hess

JOSEPH A. HESS NOTARY PUBLIC

My Commission expires: September 19, 1970