


15-065-20709-00-00

FORM CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Graham County. Sec. 5 Twp. 10S Rge. 22W (E) (W)  
Location as "NE/CNWxSWx" or footage from lines C N/2 NE SW  
Lease Owner Barnett Oil, Inc.  
Lease Name Griffith Well No. 1  
Office Address 411 First National Bank Bldg., Wichita, KS 67202  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed September 21 19 74  
Application for plugging filed September 21 19 74  
Application for plugging approved September 21 19 74  
Plugging commenced September 21 19 74  
Plugging completed September 21 19 74  
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,006 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	208'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plug #1 @ 950' w/70 sx.  
Plug #2 @ 215' w/20 sx.  
Plug #3 @ 40' w/10 sx.  
Cmt. was 50/50 pozmix 6% STATE  
(50 sx. common cmt., 50 sx.  
pozmix, 6 sx. gel.)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 30 1974  
09-30-1974  
CONSERVATION DIVISION  
Wichita, Kansas


Name of Plugging Contractor Red Tiger Drilling Company  
Address 1720 Wichita Plaza, Wichita, Kansas 67202  
(If additional description is necessary, use BACK of this sheet)

STATE OF Kansas COUNTY OF Sedgwick ss.  
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens  
1720 Wichita Plaza, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of September, 19 74

My commission expires December 28, 1977  
Notary Publics.



15-065-20709-00-00

DRILLERS LOG

No. 1 Griffith

CASING RECORD:

8-5/8" @ 208'  
w/150 sx. cmt.

TOTAL DEPTH: 4,006'

COMPANY: Barnett Oil, Inc.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: September 13, 1974

COMPLETED: September 21, 1974

DESCRIPTION:

C N/2 NE SW  
5-10S-22W  
Graham County,  
Kansas

ELEVATION: 2,341'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	780	
Sand & Shale	780	882	
Shale	882	1065	
Shale & Shells	1065	1405	
Sand	1405	1590	
Shale & Redbed	1590	1810	
Shale	1810	1882	
Anhydrite	1882	1918	
Shale	1918	2545	
Shale & Lime	2545	2740	
Lime & Shale	2740	2930	
Shale & Lime	2930	3033	
Lime & Shale	3033	3140	
Lime	3140	3850	
Shale & Lime	3850	3930	
Lime	3930	4006	

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 30 1974  
09-30-1974  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens  
Linda H. Dickens

Subscribed and sworn to before me this 25th day of September, 1974.

D'Ann Drennan  
Notary Public

My Commission Expires:

December 28, 1977

