

STATE OF KANSAS
STATE CORPORATION COMMISSION
206 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-065-22,727-00-00

LEASE NAME PARKS

WELL NUMBER #1

990' Ft. from S Section Line

1420' Ft. from E Section Line

SEC. 34 TWP. 10S RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 11-18-93

Plugging Completed 11-18-93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR SATEX ENERGY, INC.

ADDRESS 100 NE Loop 410, Ste 1380, San Antonio, TX 78216

PHONE# (210) 366-1380 OPERATORS LICENSE NO. 31342

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-18-93 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3847'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	312'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Fill w/heavy mud; set 1st plug @ 3800'-3700' w/25 sx; 2nd plug @ 1690'-1590' w/25 sx; 3rd plug @ 900'-500' w/100 sx; 4th plug @ 360'-200' w/40 sx; 5th plug @ 40'-surface w/10 sx; rathole 15 sx; Total 250 sx 60-40 posmix 6% gel 2 sx celoflake.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684


Address 150 N. Main, Ste 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Satex Energy Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Mark R. Galyon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Mark R. Galyon



RECEIVED

STATE CORPORATION COMMISSION 150 N. Main, Ste 801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO, DEC 16 1993 this 24th day of November, 19 93

Angela Woodard
CONSERVATION DIVISION Notary Public

My Commission Expires: Wichita Kansas 97

USE ONLY ONE SIDE OF EACH FORM