

15-065 - 02422-00-00

WELL LOG - RATHBUN #1

WELL OWNER: The Palmer Oil Corporation

Location: NE NE NW
Section 34-10S-21W
Graham County, Kansas
Elevation: 2187 R. B.

CONTRACTOR: The Palmer Oil Corporation

Commenced: 8/1/52
Completed: 8/13/52
RESULTS: Dry Hole

Casing Record

8 5/8" - 157' cemented 100 sacks

Shale & shells	0	157
Shale	157	231
Shale & shells	231	770
Sand	770	840
Shale & shells	840	1180
Sand	1180	1415
Shale & red rock	1415	1665
Anhydrite	1665	1710
Shale & shells	1710	2200
Lime & shale	2200	2250
Lime	2250	2325
Shale & lime	2325	2685
Shale, lime streaks	2685	2980
Shale & lime	2980	3170
Shale & shells	3170	3210
Lime	3210	3220
Lime & shale	3220	3300
Lime	3300	3756
Shale & lime	3756	3780
Lime	3780	3793 Rotary T. D.

Formation Tops (R. B.)

Heebner	3425
Lansing	3464
Arbuckle	3783

DRILL STEM TEST - 3503 - 3531 Open one hour. Recovered 93 feet water - slight trace oil. BHP 1000#.

DRILL STEM TEST - 3650 - 3671 Open one hour - very slight blow, dead in 20 minutes. Recovered 15' Rotary mud. BHP 300#

DRILL STEM TEST - 3785 - 3792 Open one hour. Recovered 3 feet water. No BHP.

This is to certify that the above is a true and correct log, according to the daily drilling reports.


THE PALMER OIL CORPORATION

PLUGGING By Edgar E. Smith
 FILE SEC 34-10-21W
 BOOK PAGE 38 LINE 21

STATE OF KANSAS)
SEDGWICK COUNTY)

ss:

Subscribed and sworn to before me, a Notary Public, in said County and State this 22nd day of August, 1952.



My Commission Expires 9/30/53

Edgar E. Smith
 Notary Public
 AUG 22 1952
 08-23-1952
 DIVISION
 Wichita, Kansas