

15-065 19180-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham

County. Sec. 34 Twp. 10S Rge. 21W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW SW

Lease Owner Nadel & Gussman

Lease Name Eaton

Well No. 1

Office Address 307 Schweiter Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-10-64 19

Application for plugging filed 7-22-64 19

Application for plugging approved 7-10-64 19

Plugging commenced 7-10-64 19

Plugging completed 7-10-64 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3850 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface hole		0	228'	8 5/8"	7-2-64	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set Plug #1 at 550' cemented with 20 sacks,

Set Plug #2 at 210', cemented with 20 sacks

Set Plug #3 at 40' with 10 sacks cement, 1/2 sack hulls.

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1964

07-23-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D & D Drilling Company, Inc.

Address 307 Schweiter Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Glenn M. Dunne, Jr.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Glenn M. Dunne, Jr.

307 Schweiter Building, Wichita, Kansas

(Address)

19 64

SUBSCRIBED AND SWORN to before me this 22nd day of July

11-18-66



Colleen Chapple
Colleen Chapple
Notary Public.

15-065-19180-00-00

ROTARY DRILLING LOG

OPERATOR: Nadel & Gussman

COMMENCED:

7-2-64

COMPLETED:

7-10-64

CONTRACTOR: D & D Drilling Co., Inc.

WELL: Eaton No. 1

ELEVATION: 2218 RB, 2215 DF, 2213 GL

LOCATION: NE NW SW Sec. 34-10S-21W

COUNTY: Graham County, Kansas

FORMATIONS	Depth	Remarks
Shale & Sand	228'	Set 10 joints of 8 5/8" surface casing at 228', cemented with 190 sacks Sunset.
Shale	920'	
Shale & Sand	1450'	
Shale	1681'	
Anhy.	1735'	
Shale & Shell	2060'	
Shale	2465'	
Shale & Lime	3477'	
Lime	3850'	
Rotary Total Depth	3850'	D & A

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1964
07-23-1964
CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

State of Kansas)

SS

County of Sedgwick)

I, Glenn M. Dunne, Jr. of lawful age, being duly and solemnly sworn on oath says: I am a resident of Wichita, Sedgwick County, Kansas, and I hereby know and on oath state, the above drilling log covering the Eaton No. 1 located in NE NW SW of Section 34-10S-21W, Graham County, Kansas, is true and correct to the best of my knowledge and belief. Further affiant saith not.

D & D Drilling Company, Inc.

By

Glenn M. Dunne, Jr.
Glenn M. Dunne, Jr.

Subscribed and sworn to before me this 22nd day of July, 1964

My Commission expires

11-18-66

Colleen Chapple
Colleen Chapple, Notary Public

