

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24837-00-00  
Spot: SWNENENW Sec/Twnshp/Rge: 24-16S-23W  
592 feet from N Section Line, 2268 feet from W Section Line  
Lease Name: TOEDMAN Well #: 1-24  
County: NESS Total Vertical Depth: 4520 feet

Operator License No.: 5144  
Op Name: MULL DRILLING COMPANY, INC.  
Address: 221 N MAIN STE 300 PO BOX 2758  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	255		

146.90

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/04/2008 5:45 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: KIRBY Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 1860' WITH 50 SX CMT. 2ND PLUG AT 1200' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 290' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE  
Date/Time Plugging Completed: 09/04/2008 7:45 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG AT 1860' WITH 50 SX CMT. 2ND PLUG AT 1200' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 290' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:

INVOICED  
DATE 9/24/08  
INV. NO. 2009060448

RECEIVED  
KANSAS CORPORATION COMMISSION


SEP 12 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01



Signed

(TECHNICIAN)

Form CP-2/3