

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01140-00-01  
Spot: NWNWNW Sec/Twnshp/Rge: 20-9S-21W  
4950 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: DAVIGNON Well #: 1  
County: GRAHAM Total Vertical Depth: 3830 feet

Operator License No.: 33937  
Op Name: NEAL LAFON REALTY INC. DBA MERI  
Address: 1475 WARD DR  
FRANKTOWN, CO 80116

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3820	0	w/unknown sxs cmt
SURF	8.625	280	0	w/unknown sxs cmt

124.48

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/05/2008 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE BORLA Company: MERIDIAN ENERGY, INC. Phone: (303) 688-4022

Proposed Plugging Method: 1st. Ordered out 400 sxs 60/40 pozmix - 4% gel - 800# hulls - c.c. on the side.  
2nd. Ordered out 200 sxs 60/40 pozmix - 4% gel.  
Attempted to clean out old well - stuck bit at 2520' - good circulation but no movement or rotation.  
Samples indicated out of casing - formation and metal cuttings.  
Anhy 1780'. Base salt 2200'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/05/2008 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech ran free point - free at 2380' - broke tubing loose at 2357'.  
Quality Oilwell Cementing pumped 100 sxs 60/40 pozmix - 4% gel with 3% c.c. - had good circulation.  
Backed tubing off at 2357'. Pulled to 1820'.  
Quality Oilwell Cementing pumped 190 sxs 60/40 pozmix - 4% gel with 400# hulls - lost circulation - followed with 50 sxs 60/40 pozmix - 4% gel with 3% c.c.  
Pulled tubing to 850'. Shut in one hour.  
Ran tubing back to 800' - tagged cement.  
Quality Oilwell Cementing pumped 60 sxs 60/40 pozmix - 4% gel - good circulation.  
Ran out of cement - ordered 200 sxs 60/40 pozmix - 4% gel - waited two hours.  
Pumped 50 sxs 60/40 pozmix - 4% gel cwc.  
PTOH. Topped 5 1/2" casing with 10 sxs - casing full.  
Pumped 10 sxs down 8 5/8" - instant pressure.  
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3820	3830		

**INVOICED**  
DATE 9/24/08  
INV. NO. 2009060454

RECEIVED  
KANSAS CORPORATION COMMISSION  
SEP 09 2008

Remarks: QUALITY OILWELL CEMENTING.

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

Form CP-2/3

SEP 08 2008

PKG

