

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21121-00-01  
Spot: E2SWNE Sec/Twnshp/Rge: 29-10S-19W  
3300 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: LARGENT-DICK Well #: 1  
County: ROOKS Total Vertical Depth: 3851 feet

Operator License No.: 33723  
Op Name: PAUL BOWMAN OIL TRUST  
Address: 801 CODELL RD  
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		1220		
PROD	4.5	3773	0	250 SX
SURF	8.625	241	0	191 SX
T1	2	1250		

Well Type: SWD UIC Docket No: D20141.0 Date/Time to Plug: 09/04/2008 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LOUIS 'DON' BOWMAN Company: PAUL BOWMAN OIL TRUST Phone: (785) 483-2627

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel -1500# hulls.  
PBTB 1325'. Plug back Marched 15, 1995 with 125 sxs 60/40 pozmix - 6% gel - 3% cc and 200# hulls.  
Operator stated a mill is stuck in the hole above plug back depth.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/04/2008 5:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 1125'. Rigged to tubing - pumped 175 sxs cement with 500# hulls - well went on a strong vacuum.  
Ordered an additional 200 sxs 60/40 pozmix - 4% gel with 1000# hulls.  
Let set two hours.  
RIH with tubing to 1125' - pumped 60 sxs 60/40 pozmix - 4% gel with 250# hulls to circulate cement to pit.  
Pulled tubing - rigged to 4 1/2" casing with a swedge - pumped 10 sxs cement.  
Max. P.S.I. 250#. S.I.P. 250#.  
Rigged to 8 5/8" casing - pumped 5 sxs 60/40 pozmix - 4% gel.  
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
1250	1300		

**INVOICED**  
DATE 9/24/08  
INV. NO. 2009060459

RECEIVED  
KANSAS CORPORATION COMMISSION  
SEP 09 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #34557.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

CM

Form CP-2/3

SEP 05 2008

TBG