

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21446-00-00
Spot: NW Sec/Twnshp/Rge: 24-33S-6W
1320 feet from N Section Line, 1320 feet from W Section Line
Lease Name: WOLFF Well #: 1
County: HARPER Total Vertical Depth: 5085 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7.875	5082		310 SX
SURF	8.625	263		180 SX

105.26

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/28/2008 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: PERFS 4392-4402, SAND TO 4342 & 5 SXS, 35 SXS 1050', 35 SXS 700' AND CIRC CMT 320'

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 08/28/2008 1:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE PLUGGED BY PUMPING 30 SXS OF CMT & 200# OF HULLS. TOC AT 3950'. REC PIPE FROM 3420' PULLED CASING TO 1050' SPOTTED 35 SXS CEMENT, PULLED CASING TO 700' SPOTTED 35 SXS CMT, PULLED CASING TO 320', CIRCD WITH 100 SXS CMT.

Perfs:

Top	Bot	Thru	Comments
4392	4402		


INVOICED

DATE 9/24/08
INV. NO. 2009060462

Remarks: QUALITY OIL WELL CEMENTING #2219 60/40 4% GEL

Plugged through: CSG

District: 02

Signed  (TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 09 2008
CONSERVATION DIVISION
WICHITA, KS

PKA