

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22984-00-00
Spot: NENWSE Sec/Twnshp/Rge: 18-11S-18W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: FRISBIE D Well #: 1
County: ELLIS Total Vertical Depth: 3700 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3699	0	200 SX
SURF	8.625	330	0	200 SX <u>120.25</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2008 1:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEN BUELLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (785) 483-1821

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 700# hulls.
Perfed at 600' - 1250' - 1850'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/27/2008 6:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3055' - spotted 75 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 2435' - pumped 100 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1691' - pumped 125 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing.
Hooked onto backside - pressured up immediately.
Pumped 10 sxs 60/40 pozmix - 4% gel to fill 5 1/2" casing.

Perfs:

Top	Bot	Thru	Comments
3473	3479		
3175	3382		
3141	3145		
3087	3095		
3072	3078		
2926	2934		

INVOICED

DATE 9/24/08

INV. NO. 2009060467

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 04 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

AUG 29 2008

PTG

ROBERT R. PRICE OPERATING, INC.

18-11-18W
NE NW SE

P.O. BOX 45442
TULSA, OK 74145

#1 "D" FRISBIE


CONTR RANGER DRILLING CO., INC.

CTY ELLIS

GEOL _____

FIELD

BEMIS SHUTTS EXT.
(3/8 W)



ELV 1902 KB SPD 7/18/82 CARD ISSUED 1/27/83
1897 GL
API 15-051-22,984

IP P 9 B0 & 31 BWPD
LKC 3230-3382 OA

LOG	Tops	Depth/Datum
ANH	1220 + 682	
TOP	2898- 996	
HEEB	3122-1220	
TOR	3140-1238	
LANS	3162-1260	
BKC	3384-1482	
CONG	3413-1511	
ARB	3470-1568	
LTD	3673-1771	
RTD	3700-1798	

8 5/8 " 330/175SX; 5 1/2 " 3699/200SX
NO DST'S
MCT - CO, PF (LKC) 3230-3382 W/1 SPF, FRAC 10,000G (15%
HCL), 72 BBLs FOAM & 185,000 SCF NITROGEN, SWB LD, GSO,
POP, P 9 B0 & 31 BWPD (GR 26.0%), 12/18/82

NOTE: ORIGINALLY FIRST REPORTED AS A "OWWO"

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS