

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04315-00-00
Spot: NENWNW Sec/Twnshp/Rge: 29-18S-13W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease Name: STOSS Well #: 2
County: BARTON Total Vertical Depth: 3435 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3423	0	wunknown sxs cmt
SURF	8.625	216	0	w/unknown sxs cmt

111.64

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/09/2008 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.
Junk in the hole.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/09/2008 11:15 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech perfed at 850' and 250'.
Express Well Service RIH to top of fish to 1500'.
Swift Services rigged to tubing - pumped 160 sxs cement to circulate cement in pit area.
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 90 sxs 60/40 pozmix - 4% gel.
Max. P.S.I. 250#. S.I.P. 200#.
Rigged to 8 5/8" casing - instant pressure 100#.

Perfs:

Top	Bot	Thru	Comments
3423	3435		
3304	3340		
3190	3240		

INVOICED
DATE 9/23/08
INV. NO. 2009060414

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 11 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES, INC.-TICKET #13850.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

Form CP-2/3

SEP 09 2008

PST

ALPINE O & R #2 STOSS 29-18-13W 52
NE NW NW

Contr. QUAKER DRILLING BARTON County

E1919 RB Comm. Comp. 1-6-61 IP 195 BOPD

Tops	Depth	Datum
ANH	825	+1094
HEFB	3082	-1163
BR IM	3167	-1248
LANS	3180	-1261
B/KC	3403	-1484
CONG	3406	-1487
ARB	3421	-1502
TD	3435	-1516

Casing
8" 216
5" 3423

DST 3190-3240/1HR, 15' M, BHP
0#

DST 3304-40/1 HR, 10' M, BHP
525#

DST 3423-35/1 HR, 360' G, 2280'
FR O, BHP 930#

CO: IST 9 BOPH/5 HBS
LAKE BARTON WEST POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS