

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-30077-00-00  
Spot: N2NENENE Sec/Twnshp/Rge: 13-17S-11W  
330 feet from N Section Line, 330 feet from E Section Line  
Lease Name: KRAFT-PRUSA UT Well #: 8-7  
County: BARTON Total Vertical Depth: 3301 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3300	0	100 SX
SURF	8.625	665	0	500 SX

107.28

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/11/2008 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 600# hulls.  
PBTD 3263'. Could not get below 2810'. Junk in the hole - casing parted.  
Operator elected all cement plug.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/11/2008 12:40 PM KCC Agent: PAT STAAB

**Actual Plugging Report:**

Log Tech perfed two shot perf at 1528' and 600'.  
Express Well Service RIH with tubing to 2800'. Swift rigged to tubing - pumped 40 sxs 60/40 pozmix - 4% gel - followed with 60 sxs 60/40 pozmix with 200# hulls mixed in.  
Pulled tubing to 1800'. Swift rigged to tubing - pumped 200 sxs 60/40 pozmix - 4% gel with 300# hulls mixed in to circulate cement up 5 1/2" casing.  
Pulled tubing - rigged to 5 1/2" casing with a swedge - pumped 100 sxs 60/40 pozmix - 4% gel to circulate cement up 8 5/8" casing.  
Shut in 8 5/8" casing. Max. P.S.I. 250#.  
Released and topped off.

**Perfs:**

Top	Bot	Thru	Comments
3237	3241		
3193	3197		
3164	3168		
3107	3113		

**INVOICED**  
DATE 9/23/08  
INV. NO. 2009060414

RECEIVED  
KANSAS CORPORATION COMMISSION  
**SEP 17 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: SWIFT SERVICES, INC. - TICKET #14646.

Plugged through: TBG

District: 04

Signed [Signature]  
(TECHNICIAN) CM

SEP 12 2008

PKT

5-223 Map No. \_\_\_\_\_

OPER SUNRAY DX OIL COMPANY


Great Bend, Kansas

WELL #7 KRAFT PRUSA UNIT -Tract 8

CONTR Stickle Drilling

FIELD Kraft Prusa (Multi-Pay) (Twin Well)

I.P. P Est 25 BOPD - Kc 3107-3241 OA



S.T.R. 13-17S-11W

SPOT 100' N/NE NE NE

CO. BARTON

ELEV 1894 KB

(KB Log)

Hb 2891 - 997

Tor 2909 -1015

BL 3000 -1106

KC 3014 -1120

LTD 3301 -1407

No DST's, RTD 3301, Sj Log, 5" @3300 w/100 ex.,

CO 3256, PF 16/3237-41, 16/3193-97, 16/3164-68,

24/3107-13 (KC), 500A & 4000 Gell X 100 Acid, 8' ld, 8

14 BF/3 hrs (20% oil), POP, Est P 25 BOPD (Waterflood oil well) from KC 3107-

3241 - COMPLETED (5-24-65)

*Data Inc*