

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19569-00-00
Spot: NWSWSENW Sec/Twnshp/Rge: 27-26S-7E
2995 feet from S Section Line, 3768 feet from E Section Line
Lease Name: YOUNG A Well #: 4
County: BUTLER Total Vertical Depth: 2737 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2250		
L1		1769		
PROD 7		2699	30 SX	88.95

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2008 8:00 AM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: JASON BURNS Company: BEREXCO Phone: (316) 265-3311

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK
Date/Time Plugging Completed: 08/13/2008 10:45 AM

Witness Type: PARTIAL
KCC Agent: DAVE WERTZ

Actual Plugging Report:

SANDED @ 2250-2081 W/4 SXS CEMENT ON TOP. PERF @ 1760', RUN TUBING TO 1780' SPOTTED 100 SACKS CMT. LOG TECH PERFED @ 250' RUN TUB TO 250' CIRCULATED CEMENT. COPELAND TICKET #32391. 175 SKS CMT, 60/40 POZMIX 4% GEL. 8-12-2008 LOG TEC TAGGED CEMENT @ 82', PERF @ 72', ESTABLISHED CIRCULATION. 8-13-2008, SWEDGED INTO 5 1/2" CSG, ESTABLISHED CIRCULATION & UNITED MIXED & PUMPED 150 SXS 60/40 POSMIX 4% GEL TO SURFACE. CEMENT CIRCULATED, PLUG DOWN @ 10:45 P.M. 8-13-2008 UNITED CEMENTING TICKET #8294

Perfs:

Top	Bot	Thru	Comments
2699	2737		
2170	2178		
2142	2162		
1769	1770		
1712	1728		

INVOICED
DATE 9/24/08
INV. NO. 2009060418

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 12 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND #32391 60/40 2%

Plugged through: TBG

District: 02

Signed

(TECHNICIAN)

PKA