

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21544-00-00  
Spot: W2NWSESW Sec/Twnshp/Rge: 34-31S-5W  
990 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: NORDHUS-DROUHARD Well #: 2  
County: HARPER Total Vertical Depth: 4662 feet

Operator License No.: 9913  
Op Name: BULLSEYE PETROLEUM, INC.  
Address: 15820 PLYMOUTH RD  
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4661		125 SX CMT.
SURF	8.625	222		165 SX CMT.   51.52
T1	2.875	4650		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/29/2008 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4570' & 5 SKS CMT, 35 XSX 1400', 35 SXS 900', CIRC 270'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/29/2008 10:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE SANDED BACK T60 4570' & CAPPED WITH 5 SKS CEMENT. THE CASING WAS RECOVERED FROM 3588', PULLED CASING TO 1400', SPOTTED 35 SXS CEMENT. PULLED CASING TO 900' SPOTTED 35 SKS CEMENT, PULLED CASING TO 270' & CIRC CMT TO TOP.

Perfs:

Top	Bot	Thru	Comments
4644	4645		
4634	4636		

**INVOICED**  
DATE 9/24/08  
INV. NO. 2009060424

Remarks: COPELAND CEMENT ACID 60/40 4% GEL

Plugged through: CSG

District: 02

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 09 2008

CONSERVATION DIVISION  
WICHITA, KS

PKT