

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-20193-00-00
Spot: NENWSW Sec/Twnshp/Rge: 20-16S-1W
2227 feet from S Section Line, 4374 feet from E Section Line
Lease Name: HUNTER Well #: 4
County: SALINE Total Vertical Depth: 2700 feet

Operator License No.: 6901
Op Name: D S & W WELL SERVICING, INC.
Address: 1822 24TH STREET
GREAT BEND, KS 67530

87.75

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/22/2008 3:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JOE STRUBIE Company: D S & W WELL SERVICING Phone: (620) 793-5838

Proposed Plugging Method: SAND TO 50' ABOVE PERFS AND CAP WITH 10 SXS CEMENT. PERFORATE CASING AT 250'. RUN TUBING TO 250' AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: GREG EVES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/22/2008 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

PRODUCTION CASING WAS PERFORATED AT 250'. RAN TUBING TO 2350' AND PUMPED 50 SXS CEMENT. PULLED TUBING TO 270' AND PUMPED 75 SXS CEMENT TO CIRCULATE TO SURFACE.

Perfs:

INVOICED
DATE 9/24/08
INV. NO. 2009060429

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 12 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENTING TICKET #C33503 TOTAL = 125 SXS 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed Greg Eves
(TECHNICIAN)

PKF