

SEP 13 2005

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

CONFIDENTIAL

Form ACO-1
September 1999
Form Must Be Typed

CONFIDENTIAL

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 5254
Name: MIDCO Exploration, Inc.
Address: 414 Plaza Drive, Suite 204
City/State/Zip: Westmont, IL 60559
Purchaser: CLARCO Gas Co., Inc.
Operator Contact Person: Earl J. Joyce, Jr.

Phone: (630) 655-2198
Contractor: Name: VAL Energy, Inc.
License: 5822

Wellsite Geologist: NONE

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____

Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____

Deepening Re-perf. Conv. to Enhr./SWD

Plug Back Plug Back Total Depth

Commingled Docket No. _____

Dual Completion Docket No. _____

Other (SWD or Enhr.?) Docket No. _____

7/8/05 7/21/05 8/2/05
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 025-21302-0000

County: Clark

NW SE SW NE Sec. 4 Twp. 34 S. R. 23 East West

990 660 feet from (S) N (circle one) Line of Section

990 660 feet from (E) W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) NE (SE) NW SW

Lease Name: Shaw Well #: 1-4

Field Name: Big Sand Creek

Producing Formation: Mississippi

Elevation: Ground: 1916 Kelly Bushing: 1926

Total Depth: 5700 Plug Back Total Depth: 5642

Amount of Surface Pipe Set and Cemented at 831 Feet

Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from _____

feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan *ALT I W HW*
(Data must be collected from the Reserve Pit) *4-24-07*

Chloride content 21,000 ppm Fluid volume 350 bbls

Dewatering method used vacuum available fluids

Location of fluid disposal if hauled offsite: _____

Operator Name: Oil Producers Inc. of Kansas

Lease Name: Leon May License No.: 8061

Quarter _____ Sec. 13 Twp. 35S S. R. 16 East West

County: Comanche Docket No.: D-28472

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: *Earl J. Joyce, Jr.*


Title: Vice-President Date: 09/13/2005

Subscribed and sworn to before me this 13th day of September

20 05

Notary Public: *Nancy L. Macyunas*

Date Commission Expires: _____



KCC Office Use ONLY

YES Letter of Confidentiality Received

If Denied, Yes Date: _____

Wireline Log Received

Geologist Report Received

UIC Distribution

CONFIDENTIAL

Side Two

KCC ORIGINAL

SEP 13 2005

CONFIDENTIAL

Operator Name: MIDCO Exploration, Inc. Lease Name: Shaw
Sec. 4 Twp. 34 S. R. 23 County: Clark

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken, Samples Sent to Geological Survey, Cores Taken, Electric Log Run, List All E. Logs Run, Cement Bond, Dual Compensated Porosity, Dual Induction. Includes table of Name, Top, Datum for Heebner, Toronto, Douglas, Lansing, BKC, Marmaton, Cherokee, Morrow, Chester, St. Gen.

CASING RECORD table with columns: Purpose of String, Size Hole Drilled, Size Casing Set (in O.D.), Weight Lbs./Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives. Rows for Surface and Production.

ADDITIONAL CEMENTING / SQUEEZE RECORD table with columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives.

PERFORATION RECORD table with columns: Shots Per Foot, PERFORATION RECORD - Bridge Plugs Set/Type, Acid, Fracture, Shot, Cement Squeeze Record, Depth.

TUBING RECORD, Date of First, Resumerd Production, SWD or Enhr., Producing Method, Estimated Production Per 24 Hours.

Disposition of Gas, METHOD OF COMPLETION, Production Interval.

Table with columns for Conductor, 32", 20", 53'.

ALLIED CEMENTING CO., INC.

ORIGINAL 20699

CONFIDENTIAL

SHIP TO P.O. BOX 31
RUSSELL, KANSAS 67665

SEP 13 2005
CONFIDENTIAL

SERVICE POINT: Medicine Lodge, KS

DATE <u>7-11-05</u>	SEC. <u>4</u>	TWP. <u>34S</u>	RANGE <u>23W</u>	CALLED OUT <u>6:00 A.M.</u>	ON LOCATION <u>8:30 A.M.</u>	JOB START <u>12:00 P.M.</u>	JOB FINISH <u>12:45 P.M.</u>
LEASE <u>Shaw</u>		WELL # <u>1-4</u>		LOCATION <u>Ashland West Edge</u>		COUNTY <u>Clark</u>	STATE <u>KS</u>
OLD OR <input checked="" type="radio"/> NEW (Circle one)				<u>LOS 2W N/1 TO</u>			

CONTRACTOR Val #2
 TYPE OF JOB Surface
 HOLE SIZE 12 1/4 T.D. 836
 CASING SIZE 8 5/8 DEPTH 831
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE 4 1/2 DEPTH 836
 TOOL _____ DEPTH _____
 PRES. MAX 400 PSI MINIMUM _____
 MEAS. LINE _____ SHOE JOINT 37 FT
 CEMENT LEFT IN CSG. 37 FT
 PERFS. _____
 DISPLACEMENT Fresh Water

OWNER Midco Exploration
 CEMENT
 AMOUNT ORDERED 225sx 65' 35:6+3% CC + 1/4# Flo Seal 100sx A+3% CC + 2% Gel
 COMMON 100 A @ 8.70 870.00
 POZMIX _____ @ _____
 GEL 2 @ 14.00 28.00
 CHLORIDE 11 @ 38.00 418.00
 ASC _____ @ _____
ALW - 225 @ 8.15 1833.75
Flo Seal 56 # @ 1.70 95.20
 @ _____
 @ _____
 @ _____
 @ _____
 @ _____
 HANDLING 351 @ 1.60 561.60
 MILEAGE 70 X 351 X .06 1474.20
 TOTAL 5280.75

EQUIPMENT
 PUMP TRUCK CEMENTER David W.
 # 343 HELPER Dennis C.
 BULK TRUCK
 # 359 DRIVER Terry G.
 BULK TRUCK
 # _____ DRIVER _____

RECEIVED
 SEP 19 2005
 KCC WICHITA

REMARKS:

Pipe on Bottom Break Circ Pump
225sx 65:35:6+3% CC + 1/4# Flo Seal
100sx A+3% CC + 2% Gel Release
Plug Displace w/ Fresh Water slow
Rate Pump Plug Float Did Hold
Cement Did Circ

SERVICE

DEPTH OF JOB 831'
 PUMP TRUCK CHARGE 0-300' 670.00
 EXTRA FOOTAGE 531' @ .55 292.05
 MILEAGE 70 @ 5.00 350.00
 MANIFOLD Head Rent @ 75.00 75.00
 @ _____
 @ _____

CHARGE TO: Midco Exploration
 STREET _____
 CITY _____ STATE _____ ZIP _____

TOTAL 1387.05

PLUG & FLOAT EQUIPMENT

8 5/8
 1-Guide Shoe @ 235.00 235.00
 1-AFU INSERT @ 325.00 325.00
 2-BASKETS @ 180.00 360.00
 2-CENTRALIZERS @ 55.00 110.00
 1-RUBBER Plug @ 100.00 100.00
 TOTAL 1130.00

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

**ANY APPLICABLE TAX
 WILL BE CHARGED
 UPON INVOICING**

SIGNATURE David H Mayfield

TAX _____
 TOTAL CHARGE ~~1387.05~~
 DISCOUNT ~~1387.05~~ IF PAID IN 30 DAYS
David H Mayfield
 PRINTED NAME

CONFIDENTIAL

ORIGINAL

ALLIED CEMENTING CO., INC. 20781

KCC

TO P.O. BOX 31
RUSSELL, KANSAS 67665

SEP 13 2005

SERVICE POINT:
MEDICINE LODGE

CONFIDENTIAL

DATE <u>7-9-05</u>	SEC. <u>4</u>	TWP. <u>34s</u>	RANGE <u>23w</u>	CALLED OUT <u>7:30 pm</u>	ON LOCATION <u>12:30 pm</u>	JOB START <u>6:45 am</u>	JOB FINISH <u>8:45 am</u>
LEASE <u>SHAW</u>	WELL # <u>1-4</u>	LOCATION <u>ASHLAND, KS, WEST EDGE, 65</u>			COUNTY <u>CLARK</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)			<u>2w, 1/4 N, W/INTO</u>				

CONTRACTOR VAL #2
 TYPE OF JOB SURFACE
 HOLE SIZE 17 1/2" T.D. 263'
 CASING SIZE 13 3/8" DEPTH 262'
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE 4 1/2" DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 250 MINIMUM 50
 MEAS. LINE _____ SHOE JOINT 30'
 CEMENT LEFT IN CSG. 30'
 PERFS. _____
 DISPLACEMENT 37 1/2 bbl. FRESH WATER

OWNER MIDCO EXPLORATION
 CEMENT
 AMOUNT ORDERED 150 SK 65' 35' 6" + 3% CC + 1/4" FLO-SEAL; 150 SK CLASS A + 3% CC + 2% GEL; 50 SK CLASS A + 3% CC (TAP OUT)
 COMMON 200 A @ 8.70 1740.00
 POZMIX _____ @ _____
 GEL 3 @ 14.00 42.00
 CHLORIDE 12 @ 38.00 456.00
 ASC _____ @ _____
ALW 150 @ 8.15 1222.50
FLO Seal 38 # @ 1.70 64.60
 _____ @ _____
 _____ @ _____
 _____ @ _____
 HANDLING 374 @ 1.60 598.40
 MILEAGE 70 X 374 X .06 1570.80
 TOTAL 5694.30

EQUIPMENT

PUMP TRUCK CEMENTER BILL M.
 # 343 HELPER DEANIS C.
 BULK TRUCK
 # 356 DRIVER STEVE K.
 BULK TRUCK
 # 363 DRIVER JASON K.

REMARKS:

PIPE ON BOTTOM, BREAK CIRCULATION, PUMP 150 SK 65' 35' 6" + 3% CC + 1/4" FLO-SEAL, 150 SK CLASS A + 3% CC + 2% GEL, STOP PUMPS, RELEASE PLUG, START DISPLACEMENT, WASH UP ON TOP OF PLUG, SEE LIFT BUMP PLUG, SHUT IN, DID NOT CIRCULATE CEMENT, TOP OUT WITH 50 SK CLASS A + 3% CC.

SERVICE

DEPTH OF JOB 262'
 PUMP TRUCK CHARGE _____ 670.00
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 70 @ 5.00 350.00
 MANIFOLD _____ @ _____
Head Rental @ 75.00 75.00
 _____ @ _____
 TOTAL 1095.00

CHARGE TO: MIDCO EXPLORATION
 STREET _____
 CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

13 3/8" Wood PLUG 1 @ 70.00 70.00
13 3/8" RAFFLE PLATE 1 @ 85.00 85.00
13 3/8" BASKET 2 @ 250.00 500.00
 _____ @ _____
 _____ @ _____
 TOTAL 655.00

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

**ANY APPLICABLE TAX
 WILL BE CHARGED
 UPON INVOICING**

SIGNATURE David H Mayfield

TAX _____
 TOTAL CHARGE ~~_____~~
 DISCOUNT ~~_____~~ IF PAID IN 30 DAYS
 PRINTED NAME David H Mayfield

ALLIED CEMENTING CO., INC.

16351

CONFIDENTIAL

KCC

ORIGINAL

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SEP 13 2005

SERVICE POINT:
Medicine Lodge

DATE <i>7-21-05</i>	SEC. <i>4</i>	TWP. <i>34S</i>	RANGE <i>23W</i>	CALLS OUT <i>9:30 AM</i>	ON LOCATION <i>11:30 AM</i>	JOB START <i>5:30 AM</i>	JOB FINISH <i>6:20 AM</i>
LEASE <i>Shaw</i>	WELL # <i>1-4</i>	LOCATION <i>Ashland, West edge</i>			COUNTY <i>Chick</i>	STATE <i>KS.</i>	
OLD OR NEW (Circle one) <i>NEW</i>			<i>65, 24, 1/5</i>				

CONTRACTOR <i>Val #1</i>	OWNER <i>Midco Exploration</i>
TYPE OF JOB <i>production</i>	
HOLE SIZE <i>7 7/8</i>	T.D. <i>5700'</i>
CASING SIZE <i>4 1/2" x 10-5</i>	DEPTH <i>5693'</i>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX <i>2000</i>	MINIMUM
MEAS. LINE	SHOE JOINT <i>39'</i>
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT <i>90 Blts 2% KCL</i>	
EQUIPMENT	
PUMP TRUCK # <i>368-265</i>	CEMENTER <i>Carl Batling</i>
	HELPER <i>David Felio</i>
BULK TRUCK # <i>353-250</i>	DRIVER <i>Thomas</i>
BULK TRUCK #	DRIVER

CEMENT		
AMOUNT ORDERED	<i>500 Gal mud-clean C</i>	
	<i>500 Gal mud-clean 9 gals Clapro</i>	
	<i>35 sx H + 10% by 10% salt & seal 8 FH</i>	
COMMON	<i>325 H</i>	@ <i>10.50</i> <i>3412.50</i>
POZMIX		@
GEL		@
CHLORIDE		@
ASC		@
	<i>500 mudclean C</i>	@ <i>1.25</i> <i>625.00</i>
	<i>Clapro 9 gals</i>	@ <i>22.90</i> <i>206.10</i>
	<i>Kol Seal 1950 #</i>	@ <i>1.60</i> <i>1170.00</i>
	<i>500 mudclean</i>	@ <i>1.00</i> <i>500.00</i>
	<i>Salt 35</i>	@ <i>7.90</i> <i>276.50</i>
		@
	<i>Gyp Seal 31</i>	@ <i>19.15</i> <i>593.65</i>
	<i>FL-160 -244 #</i>	@ <i>8.70</i> <i>2122.80</i>
HANDLING	<i>435</i>	@ <i>1.60</i> <i>696.00</i>
MILEAGE	<i>70 x 435 x .06</i>	<i>1827.00</i>
		TOTAL <i>11429.55</i>

REMARKS:

*Run Csg Drop ball for AFV shoe break
Circulation pump 500 Gal mud-clean C
500 Gal Reg mud-clean mix 30 sx H
+ Additives wash pump + lines
Release plug + Dip w/ 90 Blts 2% KCL
Land plug + Float held.
(25 sx com on loc for Pat+mouse)*

SERVICE

DEPTH OF JOB	<i>5693'</i>	
PUMP TRUCK CHARGE		<i>1610.00</i>
EXTRA FOOTAGE	@	
MILEAGE	<i>70</i>	@ <i>5.00</i> <i>350.00</i>
	<i>Head Rental</i>	@ <i>75.00</i> <i>75.00</i>
		@
		@

TOTAL *2035.00*

CHARGE TO: *Midco Exploration*
STREET _____
CITY _____ STATE _____ ZIP _____

4 1/2" PLUG & FLOAT EQUIPMENT

MANIFOLD	@	
<i>1-AFV float shoe</i>	@ <i>200.00</i>	<i>200.00</i>
<i>1-latch down plug</i>	@ <i>300.00</i>	<i>300.00</i>
<i>6-centralizers</i>	@ <i>45.00</i>	<i>270.00</i>
<i>6-turkizers</i>	@ <i>55.00</i>	<i>330.00</i>

TOTAL *1100.00*

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

SIGNATURE *David H Mayfield*

TAX _____
TOTAL CHARGE ~~_____~~
DISCOUNT ~~_____~~ IF PAID IN 30 DAYS
David H Mayfield
PRINTED NAME