

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Paxton Grant, LLC
Address: 132 N. Otsego Ave. Gaylord, MI 49735
Phone: (989) 732-9400 Operator License #: 33503
Type of Well: Gas - CM Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7/9/08 2:00 PM (Date)
by: Clayton Tittel (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 133-26292-0000
Lease Name: Inman
Well Number: C1-22
Spot Location (QQQQ): S2NE - NW - NE
355 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 22 Twp. 27 S. R. 21 East West
County: NEOSHO
Date Well Completed: 12/01/2005
Plugging Commenced: 7/9/08
Plugging Completed: 7/9/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
SURFACE	21'			8.625"		CEMENTED WITH 4 SACKS
PRODUCTION	818'			4.5"		CEMENTED WITH 95 SACKS


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED.
CEMENT WAS PUMPED INTO THE 4 1/2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 600 PSI., 70 SACKS OF CEMENT WERE PUMPED INTO THE WELL.

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: W & W PRODUCTION COMPANY License #: 5491
Address: 1150 HIGHWAY 39 CHANUTE, KANSAS 66720
Name of Party Responsible for Plugging Fees: W & W PRODUCTION COMPANY
State of KANSAS County, NEOSHO, ss.

SEP 11 2008
CONSERVATION DIVISION
WICHITA, KS

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jennifer A. Wissett
(Address) 1150 HIGHWAY 39 CHANUTE, KANSAS 66720

SUBSCRIBED and SWORN TO before me this 8TH day of SEPTEMBER, 20 08

Notary Public My Commission Expires: 10-6-2010

PKT