

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: D.S. & W. Well Servicing, Inc.
Address: 1822 24th Street
Phone: (620) 793-5838 Operator License #: 6901
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: April 10, 2008 (Date)
by: Greg Eves (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-169-20200-00-00
Lease Name: Hunter
Well Number: #5
Spot Location (QQQQ): SE - SW - SW -
344 Feet from North / South Section Line
4413 Feet from East / West Section Line
Sec. 20 Twp. 16 S. R. 1 East West
County: Saline
Date Well Completed: _____
Plugging Commenced: April 23, 2008
Plugging Completed: September 22, 2008 *KCC #19 per CP#3*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	210'	8-5/8"	210'	0'
	Production	0'	2698'	5-1/2"	2698'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran tubing to 2550'. Pumped 35 sacks 60/40 poz mix w/4% gel. Well was perforated @ 260' w/2 shots. Pulled tubing to 270'. Pumped 200 sacks w/no circulation. Ran 21 jts - tagged cement. Pulled 2 jts. Pulled tubing to 600' - pumped 70 sacks 60/40 poz w/4% gel. Circulated to surface. Pulled tubing out of hole. Rigged down. Topped well off with state-recommended ready mix.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc. License #: 6901 **RECEIVED KANSAS CORPORATION COMMISSION**
Address: 1822 24th Street, Great Bend, KS 67530 **SEP 25 2008**
Name of Party Responsible for Plugging Fees: D.S. & W. Well Servicing, Inc. **CONSERVATION DIVISION WICHITA, KS**
State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/2010

(Signature) Edward S. Nemnich
(Address) 1822 24th Street, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 23rd day of September, 20 08

Karen J. Mitchell My Commission Expires: 4/13/2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

per