

15-065-20662-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Graham County, Sec. 17, Twp. 10S, Rge. 22 (E) 22 (W)

Location as "NE/CNW&SW&" or footage from lines: NW SW SW  
Lease Owner: Murfin Drilling Company  
Lease Name: Fritts Well No. #1  
Office Address: 617 Union Center Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 21 19 74  
Application for plugging filed March 21, 1974 19 74  
Application for plugging approved 3-21-74 19  
Plugging commenced 3-21-74 19  
Plugging completed 3-21-74 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Moreland, Kansas.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3660 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	247'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug @ 1000' w/110 sx  
2nd plug @ 250' w/30 sx  
3rd plug @ 40' w/10 sx

RECEIVED  
STATE CORPORATION COMMISSION  
APR 5 - 1974  
04-05-1974  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Sun Oil Well Cementing, Inc.  
Address: Box 169, Great Bend, Kansas


STATE OF Kansas COUNTY OF Sedgwick, ss.  
James R. Daniels (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) James R. Daniels  
617 Union Center, Wichita, Kansas 67202  
(Address)

Subscribed and sworn to before me this 3rd day of April, 19 74

My commission expires \_\_\_\_\_  
BARBARA COLE, Notary Public  
My Commission Expires Sept. 5, 1976

Notary Public.



WELL LOG

15-065-20662-00-00

COMPANY Murfin Drilling Co.

SEC. 17 T. 10S R. 22W

FARM Fritts

NO. 1

LOC. NW SW SW

RIG. NO. 15


TOTAL DEPTH 3660'

COUNTY Graham

COMM. 3-17-74

COMP. 3-21-74

KANSAS



CONTRACTOR Murfin Drilling Company

CASING

20 10
15 8 5/8" @ 247' w/160 sx Sunset.
12 6
13 5

ELEVATION 2371 GL 2376 KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

40 Surf soil
165 Sand & shale
210 Sand
247 Shale
1160 Shale, cmt sand
1650 Shale sand
1914 Red bed
1940 Anhydrite
1958 Anhydrite
2370 Shale
2710 Shale
2955 Shale - Lime
3190 Shale & Lime
3330 Shale - Lime
3565 Lime
3660 Lime
3660 TD

RECEIVED
STATE CORPORATION COMMISSION
APR 5 - 1974
04-05-1974
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas
County of Sedgwick

I, James R. Daniels of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Fritts #1 well.



Signature of James R. Daniels
Signature of Barbara Cole
NOTARY PUBLIC

Subscribed and sworn to before me this 3rd day of April 1974.
BARBARA COLE, Notary Public
My Commission Expires Sept. 5, 1976