

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,290-00-00

LEASE NAME Griffith

WELL NUMBER 1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 18 TWP. 10S RGE. 22 (W) of (W)

COUNTY Graham

Date Well Completed 2-15-86

Plugging Commenced 2-15-86

Plugging Completed 2-15-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Sage Drilling Co., Inc.

ADDRESS 202 S. St. Francis, Wichita, KS 67202

PHONE# (316) 263-6139 OPERATORS LICENSE NO. 5421

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas, 2-14-86 afternoon

Is ACO-1 filed? yes If not, is well log attached? well logs are attached

Producing Formation none Depth to Top _____ Bottom T.D. 4200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	286'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

4200-4160': 9.2 ppg mud; 4160-4085': 20 sx 60-40=pozmix, 6% gel; 4085-1930: 9.2 ppg mud; 1930-1855': 20 sx. 60-40 pozmix, 6% gel; 1855-1050': 9.2 ppg mud; 1050-675': 100 sx. 60-40 pozmix, 6% gel + 1 sx. Celloflakes; 675-335': 9.2 ppg mud; 335-190': 40 sx. 60-40 pozmix, 6% gel; 190-40': 9.2 ppg mud; 40-0": 10 sx. 60-40 pozmix, 6% gel, wooden plug @ 40'; 10 sx. 60-40 pozmix,

(If additional description is necessary, use BACK of this form.)

6% gel in rat hole

Name of Plugging Contractor Sage Drilling Co., Inc. License No. 5421

Address 202 S. St. Francis, Wichita, KS 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Charles Casey Coats, P.E. (Employee of Operator) or ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Charles Casey Coats, P.E.

Charles Casey Coats

(Address) 202 S. St. Francis, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 17 day of February, 1986

Sandra Kay Hiner
Sandra Kay Hiner, Notary Public

My Commission Expires: June 5, 1988

RECEIVED
STATE CORPORATION COMMISSION

FEB 18 1986
02-18-1986
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 08-84

CANDRA KAY HINER
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 6-5-88