


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 21 Twp. 10 Rge. 22 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Theodore Gore
Lease Name Griffith Well No. 1
Office Address 400 Brown Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 17, 1956 19
Application for plugging filed June 17, 1956 19
Application for plugging approved June 17, 1956 19
Plugging commenced June 17, 1956 19
Plugging completed June 17, 1956 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1082 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	226'	
					w/135 sacks	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug at 210' with 1/2 sack hulls, 155 sacks cement, mud to 40';
set second plug with 1/2 sack hulls, 10 sacks cement, cemented to bottom of
cellar

STATE OF KANSAS
06-29-1956
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Veeder Supply and Development Co.
Address Box 201, Cherryvale, Kansas


STATE OF Kansas, COUNTY OF Montgomery, ss.
C. H. Woods (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Woods
Cherryvale, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of June, 19 56

July 11
November 1, 1956
Gles Lawson Notary Public.

PLUGGING
FILE SEC. 21 T. 10 R. 22W
BOOK PAGE 73 LINE 15



15-065-00888-00-00

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Co.
 Drilled for Theodore Gore-Veeder Supply & Dev'l. Co. Farm Griffith No. 1 Depth 4082'
 Contractor Veeder Supply & Dev'l. Co. Pipe 226' 8 5/8" casing w/135 sacks
 Location NW/4 NW/4 SE/4 Sec. 21 Twp. 10 Range 22
 Commenced June 6, 1956 Completed June 17, 1956 County Graham State Kansas

Soil, sand and shale	10	80	80	TOPS:	
Gravel and shale	80	160	80		
Shale	160	710	550	Heebner	3541
Shale and sand	710	1510	800	Lansing	3579
Shale, red bed	1510	1807	297	B. KC	3811
Anhydrite	1807	1847	40	Arbuckle	4057
Shale and shells	1847	2275	428		
Shale and lime streaks	2275	2310	35	All tops KB	2307
Shale and lime	2310	2700	390		
Lime and shale	2700	3420	720		
Lime	3420	3840	420		
Lime and shale	3840	3885	45		
Shale, cert lime	3885	3915	30		
Lime and cherty	3915	3955	40		
Cherty, shale and lime	3955	4002	47		
Streaks chert, shale, lime	4002	4075	73		
Lime	4075	4082	7		
T. D.	4082				

Dry and abandoned

AFFIDAVIT

STATE OF KANSAS)
Montgomery County) SS

C. H. Woods, of lawful age, being first duly sworn on oath, deposes and says:

THAT he has read the above and foregoing drilling log covering the Griffith #1 well located in Section 21-10-22 Graham County, Kansas, and that the same is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

BY C. H. Woods
C. H. Woods

Subscribed and sworn to before me this 21st day of June, 1956.

Oliver Lawson
Notary Public

My commission expires July 11, ~~November 1,~~ 1956.

06-29-1956

PLUGGING
 FILE SEC. 21 T. 10 R. 22W
 BOOK PAGE 73 LINE 15