


15-065-00656-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Graham County. Sec. 27 Twp. 10S Rge. (E) 24 (W)  
Location as "NE/CNW&SW&" or footage from lines C SE NW  
Lease Owner CHIEF DRILLING CO., INC.  
Lease Name SCHREINER Well No. 1  
Office Address P.O. Box 797, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 16 19 61  
Application for plugging filed October 16 19 61  
Application for plugging approved October 16 19 61  
Plugging commenced October 16 19 61  
Plugging completed October 16 19 61  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4000 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	192	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1/3 sack hulls and wooden plug at 550'  
Mixed 20 sacks cement through drill pipe.  
1/3 sack hulls and wooden plug at 180'  
Mixed 20 sacks cement through drill pipe.  
1/3 sack hulls and wooden plug at 35'  
Mixed 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 24 1961  
10-24-61  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor CHIEF DRILLING CO., INC.  
Address P.O. Box 797, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover  
P.O. Box 797, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of October, 19 61  
My commission expires June 18, 1963  
Dorothy B. John Notary Public.



WELL LOG

Chief Drilling Co., Inc.  
P.O. Box 797  
Great Bend, Kansas

No. 1 Schreiner  
C SE NW Sec. 27-10S-24W  
Graham County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 10-8-61  
Completed: 10-16-61

CASING RECORD: 8-5/8" @ 192' with 150 sacks GL-3 cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>		
Sand and Shale	0	192	2402' Gr.		
Shale	192	1090	2404' D.F.		
Sand & Shale	1090	1150	2407' K.B.		
Shale & Shells	1150	1275			
Sand	1275	1320			
Shale & Shells	1320	1600			
Sand	1600	1760			
Shale, Shells & Redbed	1760	2023			
Anhydrite	2023	2045			
Anhydrite	2045	2068			
Shale & Shells	2068	2310			
Shale	2310	2600			
Shale & Lime Streaks	2600	2690			
Lime & Shale	2690	2735			
Lime	2735	2860			
Lime	2860	3110			
Lime & Shale	3110	3225			
Lime	3225	3325			
Lime & Shale	3325	3418			
Lime	3418	4000			
Total Depth	4000				

<u>FORMATION TOPS</u>		<u>Sample</u>	<u>Log</u>
Any		2023	
Heebner		3713	3718
Toronto		3737	3742
Lansing		3753	3758
Base Kansas City		3985	3990
Total Depth		4000	4005

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SE NW Sec. 27-10S-24W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 27 1961

V. Richard Hoover, President

CONSERVATION DIVISION  
Wichita, Kansas

and sworn to before me this 25th day of October, 1961

Dorothy B. Jean, Notary Public

Commission expires: June 18, 1963

