


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 32 Twp. 10S Rge. 24WE/W
Location as "NE/CNW $\frac{1}{2}$ /SW $\frac{1}{2}$ " or footage from lines
SW NE NE

Lease Owner Tomlinson Oil Company
Lease Name HANNA "C" Well No. #3
Office Address 200 W. Douglas, Suite 1030, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed Sep. 11 1979
Application for plugging filed (verbally) Sep. 11 1979
Application for plugging approved (verbally) Sep. 11 1979
Plugging commenced Sep. 11 1979
Plugging completed Sep. 11 1979

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 4030'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 4030'
Set 1st plug at 950' with 70 sacks
2nd plug at 240' with 20 sacks
3rd plug at 40' solid bridge with 10 sacks
rathole with 5 sacks.
Cemented with 50/50 posmix, 6% gel.
Job was complete at 10:00 p.m., 9-11-79.

STATE RECEIVED
CORPORATION COMMISSION
9-19-79
SEP 19 1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 19 79.



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 08-21-82.

CONTRACTOR'S WELL LOG

OPERATOR: Tomlinson Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Hanna "C" #3
 LOCATION: SW NE NE, Section 32-10S-24W
 Graham County, Kansas
 SPUD DATE: September 05, 1979
 COMPLETION DATE: September 11, 1979

0	271	Sand and shale
271	1028	Shale and sand
1028	1611	Sand and shale
1611	1824	Sand
1824	2058	Shale
2058	2105	Anhydrite
2105	2125	Shale
2125	3027	Shale and lime
3027	3067	Lime
3067	3830	Shale and lime
3830	4030	Lime
	4030	Rotary Total Depth

Spud hole at 12:00 a.m., September 05, 1979. Drilled 272' of 12" hole. Ran 6 joints of 8-5/8" - 28# casing. Set at 268' with 180 sacks of common cement, 3% Ca.Cl., 2% gel. Pumped the plug to 250'. Cement did circulate. Plug was down at 5:00 p.m., September 05, 1979.

T.D. 4030'. Set 1st plug at 950' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Job was complete at 10:00 p.m., September 11, 1979.

SAMPLE TOPS:

Anhydrite 2058'
 B/Anhydrite 2105'

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)


RECEIVED
 STATE COMPTROLLER COMMISSION
 SEP 19 1979
 CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the Hanna "C" #3, SW NE NE, Section 32-10S-24W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 17th day of September, 1979.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.