

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-077-10004-00-02 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 1-21-1955

Well Operator: Bryce F. Hayes Oil & Gas KCC License #: 05429
(Owner / Company Name) (Operator's)

Address: PO Box 108 1081 West Highway 160 City: Attica

State: KS Zip Code: 67009 Contact Phone: (620) 254-7204

Lease: FW Grabs B-1 SWD Well #: 1 *KCCPKT per UIC* Sec. 13 Twp. 31S S. R. 9 East West

SW SW SE Spot Location / QQQQ County: Harper

330 291 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2340 2293 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # D-07,755 ENHR Docket # _____ Other: _____

Conductor Casing Size: 2 7/8" Tubing Set at: 3787' Cemented with: 180 SK 12-29-1999 Sacks

Surface Casing Size: 9 5/8 Set at: 200 Cemented with: 250 Sacks

Production Casing Size: 5 1/2 Set at: 4479 Cemented with: 250 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3905 - 3915 and 4066 - 4078 CIBP 4200'

Elevation: 1601 (G.L. / K.B.) T.D.: 4479 PBTD: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): See Attachment

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 08 2008

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

**CONSERVATION DIVISION
WICHITA, KS**

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Bryce F. Hayes

Phone: (620) 254-7204

Address: PO Box 108 1081 West Highway 160 City / State: Attica, KS 67009

Plugging Contractor: Bryce F. Hayes Oil & Gas KCC License #: 5429
(Company Name) (Contractor's)

Address: PO Box 108 Attica, KS 67009 Phone: (620) 254-7204

Proposed Date and Hour of Plugging (if known?): Wednesday September 24th, 2008

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 9/24/08 Authorized Operator / Agent: 9/24/2008 8:00 AM
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

** Well Plugged - KCC - PKT*

*Dist
2
PKT*

Plugging Instructions
By: Steve VanGiesen

Stage I

Perforate through 2 7/8" tubing and 5 1/2" casing @ 1500'.
Rig up Allied and pump down 2 7/8" tubing until have good circulation from annulus
Mix 35 sx Class A cement w/ 3% calcium chloride
Displace down 2 7/8" tubing leaving 150' in tubing
Let set up 2 hours

Stage II

Perf. @ 900' through 2 7/8" tubing and 5 1/2" casing.
Break circulation w/ fresh water.
Mix 35 sx Class A 3% calcium chloride cement and pump and displace w/ fresh water
leaving 150' in tubing
Let set for 2 hours

Stage III

Perf. @ 250' through 2 7/8" tubing and 5 1/2" casing
Break circulation w/ fresh water.
Mix Class A cement w/ 3% calcium chloride and leave Braden shut in
Displace cement up 5 1/2" until there is good cement to surface.
Shut in tubing head and open Braden head valve.
Circulate cement to surface up annulus

Job Complete

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 08 2008

CONSERVATION DIVISION
WICHITA, KS


MAGNOLIA PETROLEUM #1 F W GRABS 'B' 13-31-9W SW SW SE

Contr. HARPER County

E 1601 Comm. Comp. 1-21-55 IP 79 B0 & 8 BWPD

Tops	Depth	Datum
MISS	4354	-2753
TD	4480	-2879

Casing
 9" 200
 5" 4479
 PB 4451: PERF 60/4405-15
 1 1/2 GOPH & 1 1/2 GWPH/8 HRS:
 ACID 500: SNOILFRAC: SWB
 1 1/2 BOPH & 1 B SW PH/5 HR
 PB 4400: PERF 30/4395-4399
 60 B0 & 11B SW/21 HRS
 GRABS WEST POOL



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 KANSAS CORPORATION COMMISSION

OCT 08 2008

CONSERVATION DIVISION
 WICHITA, KS