

RECEIVED

DEC 05 2001

KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM

WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 6412
 Name: Sid Tomlinson
 Address: P.O. Box 398
 City/State/Zip: Hays, KS 67601
 Purchaser: Coop Refining
 Operator Contact Person: Sid Tomlinson
 Phone: 785 - 628-8989
 Contractor: Name: L. D. Drilling, Inc.
 License: 6039
 Wellsite Geologist: Bob O'Dell
 Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)
 If Workover/Re-entry: Old Well Info as follows:
 Operator: _____
 Well Name: _____
 Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth _____
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____
 5-22-01 5-29-01 7-08-01
 Spud Date or Date Reached TD Completion Date or
 Recompletion Date Recompletion Date

API No. 15 - 051-25089- 0000
 County: Ellis
S/2 SWNE Sec. 8 Twp. 13 S. R. 19 East West
2310 feet from S (circle one) Line of Section
1980 feet from (circle one) W Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 (circle one) NE SE NW SW
 Lease Name: Fred Slaughter Well #: 1
 Field Name: Wildcat
 Producing Formation: Lansing
 Elevation: Ground: 2077' Kelly Bushing: 2082'
 Total Depth: 3825' Plug Back Total Depth: 3761'
 Amount of Surface Pipe Set and Cemented at 255' Feet
 Multiple Stage Cementing Collar Used? Yes No
 If yes, show depth set 1444' Feet
 If Alternate II completion, cement circulated from 1444'
 feet depth to surface w/ 290 sx cmt.
60-40 Poz+8% gel
 Drilling Fluid Management Plan Out 2 RGR 9/5/07
 (Data must be collected from the Reserve Pit)
 Chloride content 1500 ppm Fluid volume 540 bbls
 Dewatering method used evaporation
 Location of fluid disposal if hauled offsite:
 Operator Name: _____
 Lease Name: _____ License No.: _____
 Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
 County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Sid Tomlinson
 Title: OPERATOR Date: 12-04-01
 Subscribed and sworn to before me this 4th day of Dec.
19 2001.
 Notary Public: Dianna Leiker
 Date Commission Expires: 2-6-2003

KCC Office Use ONLY

Letter of Confidentiality Attached
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution



Operator Name: Sid Tomlinson Lease Name: Fred Slaughter Well #: 1
 Sec. 8 Twp. 13 S. R. 19 East West County: Ellis

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <i>(Attach Additional Sheets)</i>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	Sample
Samples Sent to Geological Survey	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Name	Top	Datum
Cores Taken	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Anhydrite	1418	+ 664
Electric Log Run <i>(Submit Copy)</i>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Topeka	3129	-1047
List All E. Logs Run:		Heebner	3369	-1287
ELI ran Dual Induction Log, and Compensated Density/Neutron. Cased hole Cement Bond Log. Geological Well Report attached.		Lansing	3413	-1331
		Marmaton	3694	-1612
		Arbuckle	3767	-1685

CASING RECORD <input checked="" type="checkbox"/> New <input checked="" type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs. / Ft.	Selling Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4"	8 5/8"	20#	255'	60/40 Poz	160	2% Gel, 3% CC
Production	7 7/8"	4 1/2"	10.5 & 11.6	3798 KB	ACS	135	500 gal WFR flu 5% Gilsonite

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input checked="" type="checkbox"/> Perforate <input checked="" type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone	1442-surf	60-40 poz	290	8% gel, 1/4# / sack flocele

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
1	3452 & 3469 , treat with 500 gal 15% MCA acid		
4	3550-54, 3574-78, 3601-04 3619-22	treat 4000 gals 15% acid with spacers of rock salt & acid flakes	

TUBING RECORD		Size	Set At	Packer At	Liner Run	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
		2 3/8	3742			
Date of First, Resumed Production, SWD or Enhr.			Producing Method			
7-08-01			<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity	
	9	-0-	trace		35	

Disposition of Gas: Vented Sold Used on Lease *(If vented, Sumit ACO-18.)*

METHOD OF COMPLETION: Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval: _____

ALLIED CEMENTING CO., INC.

6337

Federal Tax I.D. [REDACTED]

ORIGINAL

REMIT TO: P.O. BOX 31
RUSSELL, KANSAS 67665SERVICE POINT: R

DATE <u>5/23/01</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>12:00 A.M.</u>	JOB START	JOB FINISH <u>2:30 P.M.</u>
LEASE <u>Slaughter</u>	WELL # <u>1</u>	LOCATION <u>40 cementa N to Emmeron</u>			COUNTY <u>Ellis</u>	STATE <u>Ks</u>	
OLD OR <u>NEW</u> (Circle one)				<u>3w 1s 1 1/2 B 5 FUTO</u>			

CONTRACTOR

TYPE OF JOB Surface

HOLE SIZE 12 1/4 T.D. 258'

CASING SIZE 8 5/8 DEPTH

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG. 10'

PERFS.

DISPLACEMENT 110 1/4 Bbl

EQUIPMENT

PUMP TRUCK CEMENTER Paul

127 HELPER Tason

BULK TRUCK

279 DRIVER Clen

BULK TRUCK

DRIVER

OWNER

CEMENT

AMOUNT ORDERED 1100 @ 40 300 CC
240 CC

COMMON	<u>96</u>	@	<u>6.65</u>	<u>638.40</u>
POZMIX	<u>64</u>	@	<u>3.55</u>	<u>227.20</u>
GEL	<u>3</u>	@	<u>10.00</u>	<u>30.00</u>
CHLORIDE	<u>5</u>	@	<u>30.00</u>	<u>150.00</u>
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>168</u>	@	<u>1.40</u>	<u>235.20</u>
MILEAGE	<u>48/SK</u>	/MILE		<u>100.00</u>

RECEIVED

DEC 0.5 2001

TOTAL 1330.40

REMARKS:

Cement Circulated!

DEPTH OF JOB

PUMP TRUCK CHARGE 520.00

EXTRA FOOTAGE @

MILEAGE 10 @ 3.00 30.00

PLUG 8 5/8 @ 45.00

TOTAL 595.00

CHARGE TO: Sid Tomilson

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE _____

PRINTED NAME _____

ALLIED CEMENTING CO., INC.

6342

Federal Tax I.D. [REDACTED]

ORIGINAL

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: R

DATE <u>5/29/01</u> <u>Fred</u>	SEC.	TWP.	RANGE	CALLED OUT	ON LOCATION <u>6:00 p.m.</u>	JOB START	JOB FINISH <u>9:30 p.m.</u>
LEASE <u>Slaughter</u>	WELL # <u>1</u>	LOCATION <u>Yocemento 3N 3W 1S</u>			COUNTY <u>Ellis</u>	STATE <u>Ks</u>	
OLD OR <u>NEW</u> (Circle one)		<u>1 1/2 E S INTO</u>					

CONTRACTOR L-D

TYPE OF JOB Long string

HOLE SIZE 7 7/8 PD. 3825

CASING SIZE 4 1/2 DEPTH 3799.40

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 20.23

CEMENT LEFT IN CSG.

OWNER

CEMENT

AMOUNT ORDERED 150 ASC 590 Gal

500 Gal WFR2

PERFS.

DISPLACEMENT 59 1/2 Bbl

COMMON	@		
POZMIX	@		
GEL	@		
CHLORIDE	@		
ASC	<u>150</u>	@ <u>8.50</u>	<u>1275.00</u>
Gilsonite	<u>750#</u>	@ <u>50¢</u>	<u>375.00</u>
WFR-2	<u>500 gals</u>	@ <u>1.00</u>	<u>500.00</u>
HANDLING <u>165</u>	@	<u>1.40</u>	<u>181.50</u>
MILEAGE <u>44.5x</u>	@	<u>1.00</u>	<u>445.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Paul

177 HELPER Bill

BULK TRUCK

282 DRIVER Glen

BULK TRUCK

DRIVER

RECEIVED

TOTAL 2431.50

DEC 0.5 2001

KCC WICHITA SERVICE

REMARKS:
500 Gal WFR2
135sx Displaced w/ 59 1/2 Bbl.

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>1180.00</u>
EXTRA FOOTAGE	@		
MILEAGE <u>10</u>	@	<u>3.00</u>	<u>30.00</u>
PLUG <u>4 1/2 TRP</u>	@		<u>48.00</u>

TOTAL 1208.00

CHARGE TO: Sid Tomlinson

STREET

CITY STATE ZIP

FLOAT EQUIPMENT

	@		
	@		
	@		
	@		
	@		

TOTAL

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX

TOTAL CHARGE

DISCOUNT IF PAID IN 30 DAYS

SIGNATURE T.C. Larson

T.C. LARSON

PRINTED NAME

ALLIED CEMENTING CO., INC.

5655

Federal Tax I.D.# [REDACTED]

ORIGINAL

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

At Bend

DATE <u>6-7-01</u>	SEC. <u>8</u>	TWP. <u>13</u>	RANGE <u>19</u>	CALLED OUT <u>12:30 PM</u>	ON LOCATION <u>3:30 PM</u>	JOB START <u>4:00 PM</u>	JOB FINISH <u>7:15 PM</u>
LEASE <u>Fred Slaughter</u>	WELL # <u>1</u>	LOCATION <u>1-70+ Yocemento Exit - Sta 40 Hwy</u>			COUNTY <u>Ellis</u>	STATE <u>Ka</u>	
OLD OR <u>NEW</u> (Circle one)				<u>3W, 1 1/2 N, 17 1/2 E, S 2 E / into</u>			

CONTRACTOR Express Well Service
 TYPE OF JOB Port Collar
 HOLE SIZE _____ T.D. _____
 CASING SIZE 4 1/2" DEPTH _____
 TUBING SIZE 2" DEPTH 3220'
 DRILL PIPE _____ DEPTH _____
 TOOL Port Collar DEPTH 1443'
 PRES. MAX 1500# MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER Sarner
 CEMENT
 AMOUNT ORDERED 350 lbs 60/40, 8 1/2 Mesh, 1/4" Pore / sh, 40 Mesh, like sand, (used 290 lbs cement)
 COMMON 174 @ 6.65 1157.10
 POZMIX 116 @ 3.55 411.80
 GEL 24 @ 10.00 240.00
 CHLORIDE _____ @ _____
SAND 1 @ 5.75 5.75
FLO-SEN 73# @ 1.40 102.20
 _____ @ _____
 _____ @ _____
 HANDLING 381 @ 1.10 419.10
 MILEAGE 216 _____ 396.24

EQUIPMENT

PUMP TRUCK CEMENTER Tom D
 # 181 HELPER Bob B
 BULK TRUCK
 # 344-112 DRIVER Larry H.
 BULK TRUCK
 # _____ DRIVER _____

RECEIVED
 DEC 0.5 2001
 KCC WICHITA SERVICE
 TOTAL \$ 2732.19

REMARKS:

Set Bridge Plug @ 325'. Tubing @ 3220'
Loaded Hole, started Bridge Plug to 1500'
Spotted 1 lb Sand on Bridge Plug, pulled
Tubing and found Port Collar. Mixed 4 lb
Med. Pore to 400' Opened Port Collar
Mixed 290 lbs 60/40 8 1/2 Mesh 1/4" Pore / sh.
Cement Circulated. Displaced 5 1/2 bbls.
Closed Port Collar. Pressured to 1500' & Held.
Run 5 1/2" tubing & worked cut. Ran tubing and
Circulated Sand off Bridge Plug.

DEPTH OF JOB 3220'
 PUMP TRUCK CHARGE _____ 650.00
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 216 @ 3.00 78.00
 PLUG _____ @ _____
 _____ @ _____
 _____ @ _____
 TOTAL \$ 728.00

CHARGE TO: Sid Tomlinson
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL _____
 TAX _____
 TOTAL CHARGE \$ 3460.19
 DISCOUNT \$ 346.02 IF PAID IN 30 DAYS

SIGNATURE T.C. Larson
 Witnessed By Fred Brown

T.C. LARSON
 PRINTED NAME
Net \$ 3114.17