



ORIGINAL

Side Two

Operator Name: Sunwest Petroleum, Inc. Lease Name: Gene Denny Well #: 7-2
Sec. 7 Twp. 34 S. R. 15 East West County: Montgomery

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken (Attach Additional Sheets)
Samples Sent to Geological Survey
Cores Taken
Electric Log Run (Submit Copy)
List All E. Logs Run:
RECEIVED
NOV 02 2001
KCC WICHITA
Log Formation (Top), Depth and Datum
Sample
Name Top Datum
Rowe 1318

CASING RECORD
Report all strings set-conductor, surface, intermediate, production, etc.
Table with columns: Purpose of String, Size Hole Drilled, Size Casing Set (In O.D.), Weight Lbs. / Ft., Setting Depth, Type of Cement, # Sacks Used, Type and Percent Additives

ADDITIONAL CEMENTING / SQUEEZE RECORD
Table with columns: Purpose, Depth Top Bottom, Type of Cement, #Sacks Used, Type and Percent Additives

PERFORATION RECORD - Bridge Plugs Set/Type
Specify Footage of Each Interval Perforated
Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)
Depth
4 Rowe Frac Acid 1318-1320.5
500gal. 15% HCL Acid
1000 BLS Fluid

TUBING RECORD
Size Set At Packer At Liner Run Yes No

Date of First, Resumed Production, SWD or Enhr. Producing Method
Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours
Oil Bbls. Gas Mcf Water Bbls. Gas-Oil Ratio Gravity

Disposition of Gas METHOD OF COMPLETION Production Interval
Vented Sold Used on Lease Open Hole Perf. Dually Comp. Commingled
Other (Specify)

**BLUE STAR  
ACID SERVICE, INC.**

PO Box 103  
Eureka, Kansas 67045

Cementing Ticket  
and Invoice Number

15-125-30041  
**ORIGINAL**  
No. 3044

Date	Customer Order No.	Sect.	Twp.	Range	Truck Called Out	On Location	Job Began	Job Completed
10-17-01		7	345	15E	7:00 AM	8:45 AM	9:15 AM	11:00 AM
Owner Sunwest Oklahoma Inc.		Contractor Shields Well Service			Charge To Sunwest Oklahoma Inc.			
Mailing Address 17776 Preston Road		City Dallas			State TX 75252			
Well No. & Form Denny # 7-2		Place		County Montgomery		State KS		
Depth of Well 1495'	Depth of Job 1467'	Casing (New) (Used)	Size 4 1/2"	Weight 10.5"	Size of Hole Amt. and Kind of Cement 6 3/4" 175 SKS	Cement Left in casing by	Request Necessity	0 feet
Kind of Job Longstring					Drillpipe	Rotary Cable		AIR Truck No. #12

Price Reference No.	# 1
Price of Job	665.00
Second Stage	
Mileage	180.00
Other Charges	
Total Charges	845.00

Remarks: Rig up to 4 1/2 casing w/ wash head. Break circulation w/ fresh water. Wash down 10' to T.D. of 1467'. Pump 15 bbl gel flush. Brought gel to surface. Circulate for 30 minutes to clean hole. Pump 15 bbl dye water mixed 175 SKS thick set cement w/ 1/4" flocele per/sk. Wash out pump & lines. Shut down. Release plug. Displace w/ 23.3 bbl fresh water. Final pumping pressure 800 PSI. Bump plug to 1300 PSI. Check float. Float held. Shut casing in @ 0 PSI. Good cement returns to surface. Job complete. Rig down.

Cementer: Kevin McCoy  
Helper: Brad - Jim  
District: EUREKA  
State: KS  
The above job was done under supervision of the owner, operator, or his agent whose signature appears below.  
M. J. [Signature]  
Agent of contractor or operator

THANK YOU

Sales Ticket for Materials Only

Quantity Sacks	BRAND AND TYPE	PRICE	TOTAL
175 SKS	Thick Set Cement	10.75	1881.25
50 #	Flocele 1/4" per/sk	1.00	50.00
RECEIVED			
300 #	Gel Flush	9.50	28.50
OCT 24 2001 KCC WICHITA			
3	4 1/2 x 6 3/4 Centralizers	26.00	78.00
1	4 1/2 Float Shoe Flapper Valve	110.00	110.00
1	4 1/2 Top Rubber Plug	35.00	35.00
Plugs		175 SKS Handling & Dumping	.50
		9.6 Tons Mileage 80	.80
Sub Total			3729.65
Delivered by Truck No. #3			Discount
Delivered from EUREKA			Sales Tax 5.9%
Signature of operator: Kevin McCoy			Total
			220.05
			3,949.70