

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: First National Oil 92020
Address: 2340 Tampa Ave, suite H, El Cajon, CA
Phone: (619)697-9595 Operator License #: 6230

API Number: 15-081206660001
Lease Name: Woods - Jacob
Well Number: 1-1

Type of Well: Gas Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): NW - NW - NE
4974 Feet from North / South Section Line
2270 Feet from East / West Section Line

The plugging proposal was approved on: 9/22/08 (Date)
by: Jack McKlaske (KCC District Agent's Name)

Sec. 1 Twp. 30 S. R. 31 East West
County: Haskell

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Date Well Completed: 1/16/1991
Plugging Commenced: 9/22/08
Plugging Completed: 9/25/08

Producing Formation(s): List All (If needed attach another sheet)
Chase Depth to Top: 2656 Bottom: 2666 T.D. 2720
Chase Depth to Top: 2670 Bottom: 2682 T.D. 2720
Chase Depth to Top: 2688 Bottom: 2710 T.D. 2720
2702 2710 2720

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	822	8 5/8	1/16/91	None
		0	2807	5 1/2	1/16/91	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

We moved in Log-Tech, set CIBP 2595' to 96' w/ 2 sacks cement, perfoed from 840' to 842' 25BS pf. Moved in Allied and pumped 100 sacks of 60/40, 4% gel + circulated up casing, pumped 40 sacks 60/40, 4% gel down surface. Did not circulate. Shut down for day. Day 2: TIH w/ tubing 8 joints. Circulate 30 sacks cement up casing. Hooked up to back side and pumped 25 sacks down casing. Pressure up to 1000 pounds. Shut down.

Name of Plugging Contractor: Eldredge Well Service License #: 32721
Address: PO Box 549, Satanta, KS 67870

RECEIVED
KANSAS CORPORATION COMMISSION


Name of Party Responsible for Plugging Fees: First National Oil
State of Florida County, Seminole, ss.

OCT 14 2007

Agricultural Energy Services (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

CONSERVATION DIVISION
WICHITA, KS

(Signature) [Signature]
(Address) 1755 W. Broadway St, Ste 6, Oriedo, FL 32765



and SWORN TO before me this 8th day of October 2008
[Signature] My Commission Expires: 10/22/2009

[Handwritten initials]