

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Tengasco, Inc.
Address: PO Box 458 Hays, KS 67601
Phone: (785) 625-6374 Operator License #: 32278
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8-4-08 (Date)
by: Dodge City District Office (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LKC Depth to Top: 3397' Bottom: 3557' T.D. 3637'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 165-21155-00-00
Lease Name: Schwindt Farms
Well Number: #1
Spot Location (QQQQ): NE - NE - NE -
330' Feet from North / South Section Line
330' Feet from East / West Section Line
Sec. 23 Twp. 17 S. R. 18 East West
County: Rush
Date Well Completed: 1-8-84
Plugging Commenced: 8-4-08
Plugging Completed: 8-4-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
LKC	Oil/ wtr	1219'	0	8-5/8"	12-3-83	
		3669'	0'	4-1/2"	12-16-83	2035' 8-4-08

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded back to 3126'. Spotted 4 sx cmt on sand. Backed off csg. 1st plug @ 1219' w/ 10sx gel & 50 sx cmt, 2nd plug @ 500'w/ 50 sx 3rd plug @ 40' w/ 30 sx cmt. 134 total sx 60/40 poz 4% gel. Recovered 2035' 4-1/2" csg.

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Wildcat Well Services License #: 33612
Address: PO Box 961 Hays, KS 67601

OCT 14 2008

Name of Party Responsible for Plugging Fees: Tengasco, Inc.
State of Ellis County, Kansas, ss.


CONSERVATION DIVISION
WICHITA, KS

Gary Wagner - Production Manager

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary Wagner

(Address) PO Box 458 Hays, KS 67601



Subscribed and SWORN TO before me this 9th day of Oct, 2008
Linda K. Pfannenstiel My Commission Expires: 2/15/2012
Notary Public