

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Tengasco, Inc.  
Address: PO Box 458 Hays, KS 67601  
Phone: (785) 625-6374 Operator License #: 32278  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 8-20-08 (Date)  
by: Dodge City District Office (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
LKC Depth to Top: 3248 Bottom: 3430 T.D. 3495  
Toronto Depth to Top: 3215 Bottom: 3218 T.D. 3495  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 165-21733-00-00  
Lease Name: Andre  
Well Number: #1  
Spot Location (QQQQ): SW - NW - NE -  
990 Feet from  North /  South Section Line  
2310' Feet from  East /  West Section Line  
Sec. 28 Twp. 16 S. R. 16  East  West  
County: Rush  
Date Well Completed: 11-14-01  
Plugging Commenced: 8-21-08  
Plugging Completed: 8-21-08

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |          | Casing Record (Surface Conductor & Production) |    |        |          |               |
|---------------------------|----------|--|----|--------|----------|---------------|
| Formation                 | Content  | From   | To | Size   | Put In   | Pulled Out    |
| LKC                       | Oil/ wtr | 1066'  | 0  | 8-5/8" | 11-15-01 |               |
| Toronto                   | Oil/wtr  | 3574'  | 0' | 4-1/2" | 11-22-01 | 1603' 8-21-08 |
|                           |          |  |    |        |          |               |
|                           |          |  |    |        |          |               |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded back to 2550'. Spotted 4 sx cmt on sand. Backed off csg. 1st plug @ 1090' w/ 10sx gel & 50 sx cmt, 2nd plug @ 500'w/ 50 sx  
3rd plug @ 40' w/ 20 sx cmt. 124 total sx 60/40 poz 4% gel. Recovered 1603' 4-1/2" csg.

Name of Plugging Contractor: Wildcat Well Services License #: 33612  
Address: PO Box 961 Hays, KS 67601


RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 14 2008

Name of Party Responsible for Plugging Fees: Tengasco, Inc.  
State of Ellis County, Kansas, ss.

CONSERVATION DIVISION  
WICHITA, KS

Gary Wagner - Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Gary Wagner  
(Address) PO Box 458 Hays, KS 67601

SUBSCRIBED and SWORN TO before me this 9th day of Oct, 2008  
Linda K. Pfannenstiel My Commission Expires: 2/5/2013  
Notary Public

PPT