

Amended

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

00-02

Lease Operator: Jason Oil Company, LLC

Address: PO Box 701, Russell, KS 67665

Phone: (785) 483-8027 Operator License #: ~~5672X~~ 33813

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Case Morris (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-167-22144-0001

Lease Name: Gross A

Well Number: 1

Spot Location (QQQQ): SW - NE - NW - NE
4674 Feet from North / South Section Line

1942 Feet from East / West Section Line

Sec. 5 Twp. 15 S. R. 13 East West

County: Russell

Date Well Completed: 7-11-83

Plugging Commenced: 06-19-08

Plugging Completed: 06-23-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	684	
				5 1/2	3167	1600

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bridge at 575', knocked out bridge, tagged tubing at 2575', dug cellar, unpacked casing head, set floor, pulled slips, had 16" stretch, ripped casing at 2010', worked pipe, pulled slip collar off casing, welded new collar on casing, ripped casing at 1840', worked pipe, ripped casing at 1600', pipe came free, pulled casing up to 1250', pumped 125 sacks, 300# hulls at 1250', pulled casing up to 700', pumped 170 sacks, 200# hulls to surface, pulled casing out, topped off with 25 sacks.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Jason Oil Company, LLC


OCT 20 2008

State of KANSAS County, Russell, ss.

CONSERVATION DIVISION
WICHITA, KS

James L. Schoenberger (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]

(Address) P. O. Box 701, Russell, KS 67665-0701

SUBSCRIBED and SWORN TO before me this 9th day of October, 2008

Fred Weigel, Jr.
Fred Weigel, Jr. Notary Public My Commission Expires: 7-18-2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]