

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: McCoy Petroleum Corporation

Address: 8080 E. Central, Suite #300, Wichita, KS 67206-2366

Phone: 316-636-2737 x 104 Operator License # 5003

Type of Well: Oil Docket #: \_\_\_\_\_

(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8/11/08 (Date)

by: Jeff Klock (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Miss \_\_\_\_\_ Depth to Top: 4414' Bottom: 4424' T.D. 4424'  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number 15-077-00855 - 00 - 00

Lease Name: WINGATE #1 KCC PLOT

Well Number: #1-1

Spot Location (QQQQ): NE NE SW

2310 Feet from  North /  South Section Line

2310 Feet from  East /  West Section Line

Sec 1 Twp 31 S. Rng. 9  East  West

County: Harper

Date Well Completed: 12/4/59

Plugging Commenced: 9/30/08

Plugging Completed: 10/2/08

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |         | Casing Record (Surface Conductor & Production) |    |        |        |            |
|---------------------------|---------|--|----|--------|--------|------------|
| Formation                 | Content | From   | To | Size   | Put In | Pulled Out |
|                           |         |  |    | 8 5/8" | 405'   | None       |
|                           |         |  |    | 5 1/2" | 4459'  | 2080'      |
|                           |         |  |    |        |        |            |
|                           |         |  |    |        |        |            |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

9/30/08: MIRU. Pulled 2080' of 5 1/2" production casing. Loaded hole with sand to 4360'. Ripped casing at 2410' and wouldn't come free. Ripped casing at 2290' and wouldn't come free. Ripped casing at 2080' and pipe came free. Pulled casing up to 1400' and pumped 35 sacks cement. Pulled casing up to 950' and pumped 35 sacks cement. Pulled to 500' and pumped 35 sacks cement. Pulled casing up to 250' and pumped 90 sacks to surface. Pulled rest of casing. Total cement was 195 sacks of 60/40 pozmix and common with 4% gel. Topped off with 15 sacks dry cement.


Name of Plugging Contractor: Quality Well Service License #: 31925

Address: 190th US 56 Highway, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation

State of Kansas County, Sedgwick, ss.

Scott Hampel - Employee of Operator (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Scott Hampel

(Address) 8080 E. Central, Suite #300, Wichita, KS 67206-2366

SUBSCRIBED and SWORN TO before me this 16th day of October 20 08

Brent B Reinhardt My Commission Expires: 12/7/2011  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 17 2008  
CONSERVATION DIVISION  
WICHITA, KS

*[Handwritten initials]*