

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Trans Pacific Oil Corporation  
Address: 100 S. Main, Suite 200, Wichita, KS 67202  
Phone: (316) 262-3596 Operator License #: 9408  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)* *(If SWD or ENHR)*  
The plugging proposal was approved on: 10/14/08 (Date)  
by: Ray Dinkle (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Lansing Depth to Top: 2854' Bottom: 2859' T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-167-20547-00-00  
Lease Name: Hines  
Well Number: #4  
Spot Location (QQQQ): SE - SE - SW -  
660' Feet from  North /  South Section Line  
2970' Feet from  East /  West Section Line  
Sec. 23 Twp. 14S S. R. 11  East  West  
County: Russell  
Date Well Completed: 10/14/08 *KCC PKT*  
Plugging Commenced: 9/12/08  
Plugging Completed: 10/14/08 *Accl Spud 10/27/08*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Express Well Serv MIRU. Pull rods, rods hang up approx 350'. (100 rods) back off 11 rods. Rig over for tbg. Csg is parted @ braden head, tbg is parted 10.5 jts. Rod pin looking up.  
GIH w/fishing tool to fish rods in csg. Fish 2 rods, 4' pony and 2 x 1.5 x 10' pump. Lay rods off rod horses and RDMO. Pull tbg and wash pipe. Run tbg to 627'.  
Pull tbg, had welder plate top of 8 5/8 to 4 1/2 csg and put in collar to pressure surface csg. SD. GIH w/tbg, not able to get out of pipe. Allied Cementing cemented @ 410'.  
w/350 sxs 60/40 Poz mix 4% gel 1/4% flo seal, 150# Hulls. To Plug and Abandon SI. RDMO.

Name of Plugging Contractor: Express Well Service Klima Well Services Inc License #: 6426 7023  
Address: P.O. Box 19, Victoria, KS 67671-0019 *KCC PKT Per CP 2/3*

Name of Party Responsible for Plugging Fees: Trans Pacific Oil Corporation

State of Sedgwick County, Kansas, ss.

Glenna Lowe (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Glenna E. Lowe

(Address) 100 S. Main, Suite 200, Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 15th day of October, 2008  
Colleen M. Powell My Commission Expires: 6-2-2009  
Notary Public

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 17 2008  
CONSERVATION DIVISION  
WICHITA, KS

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas

COLLEEN M. POWELL  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 6-2-2009