

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

RECEIVED

KANSAS CORPORATION COMMISSION

Form CP-4

December 2003

OCT 16 2008

Type or Print on this Form
Form must be Signed
All blanks must be Filled

CONSERVATION DIVISION
WICHITA, KS

Lease Operator: Oxy USA, Inc

Address: PO Box 2528 Liberal KS 67905

Phone: 620.629 4200 Operator License #: 5447

Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 9-12-08 (Date)

by: Richard Lacy (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Council Grove Depth to Top: 2825 Bottom: 2877 T.D. 3005

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-129-20366-00-00

Lease Name: Morgan B

Well Number: 2

Spot Location (QQQQ): _____ SE

1327 Feet from ☐ North / ☒ South Section Line

1327 Feet from ☒ East / ☐ West Section Line

Sec. 10 Twp. 34 S. R. 40 ☐ East ☒ West

County: Morton

Date Well Completed: 4-28-79 spud

Plugging Commenced: 9-15-08

Plugging Completed: 9-15-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	539	-
				4 1/2	3001	620

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Attempt to pump mud down 4 1/2. Press. up to 1700 PSI. Weather-
ford it bridge @ 1172 w/guage ring. Set CIBP + 2 sx cmt. from
1172 to 1152. Shot & pull 4 1/2 to 570. Circ. hole w/mud & mixed
50 sx plug 570 to 420 10 sx 40 to 0 Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151

Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Oxy USA Inc. PO Box 2528 1701 N. Kansas Liberal, KS 67905

State of Kansas County, Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly
sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the
same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS 67905

SUBSCRIBED and SWORN TO before me this 13 day of Oct. 2008

Anita Peterson My Commission Expires: Oct. 1, 2009
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

