

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Edgewood Land & Cattle Co. Address: 618 N Westchester Dr. Andover, KS 67002 Phone: (316) 733-2248 Operator License #: 30471 Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR) The plugging proposal was approved on: 09/18/08 by: Mike Heffern (KCC District Agent's Name) Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No Producing Formation(s): List All (If needed attach another sheet) Bartlesville Depth to Top: 2270 Bottom: 2355 T.D. 2355

API Number: 15-073-24005-00-00 Lease Name: Browning Well Number: 22 Spot Location (QQQQ): N/2 - NE - SE - 2310 Feet from [] North / [X] South Section Line 660 Feet from [X] East / [] West Section Line Sec. 19 Twp. 22 S. R. 10 [X] East [] West County: Greenwood Date Well Completed: 03/27/05 Plugging Commenced: 09/18/08 Plugging Completed: 09/20/08

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Bartlesville, Surface, 200', 8 5/8, 03/13/05, None. Row 2: Bartlesville, 200', 2352', 5 1/2, 03/18/05, 560'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

(09/18/08) Spot 20 sacks at perfs 2312-2328' - Spot gel spacer to 1000' - Spot 15 sacks cement at 1000' - Displace with 5 1/2 plug

(09/20/08) Run 254 tubing cement to surface with 100 sacks 60/40 pozmix 4% gel

135 sacks 60/40 pozmix 4% gel total

RECEIVED KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Consolidated Oil Well Services, L.L.C. License #: 33961 OCT 16 2008

Address: P.O. Box 884, Chanute, KS 66720 CONSERVATION DIVISION WICHITA, KE

Name of Party Responsible for Plugging Fees: Edgewood Land & Cattle Co.


State of Kansas County, Greenwood, ss.

Harry Patterson (Company Agent) (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Harry Patterson (Address) 618 N Westchester Dr. Andover, KS 67002

SUBSCRIBED and SWORN TO before me this 8th day of October, 2008

Notary Public My Commission Expires: 8-11-2010



Handwritten initials/signature



CONSOLIDATED
Oil Well Services, L.L.C.

ENTERED

TICKET NUMBER 19477
LOCATION Eureka
FOREMAN Russell McCoy

PO Box 884, Chanute, KS 65720
620-431-9210 or 800-457-3576

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9-18-08	2523	Browning # 22	19	22	10	Grant

CUSTOMER	TRUCK #	DRIVER	TRUCK #	DRIVER
Edge Wood Land & Cattle Co.	520	CLIFF		
618 Westchester Dr.	441	Dave		
CITY: Andover	485	Alan		
STATE: KS	436	Chris		
ZIP CODE: 67002				

JOB TYPE PTA HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT 5 1/2
 CASING DEPTH _____ DRILL PIPE _____ TUBING 2 7/8 OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT IN CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: 9-18-08 SPOT 20 SKs Down 5 1/2 At Perfs 2312 - 28
SAT Gel SPACER TO 1000'
SPOT 15 SKs cement At 1000' Displace w/ 5 1/2 Plug
Close Well IN.

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 16 2008
CONSERVATION DIVISION
WICHITA, KS

9-20-08 Run 254 Tubing cement TO Surface w/ 100 SKs
60/40 Pozmix 4% Gel GOOD cement TO Surface
135 SKs 60/40 4% Gel TOTAL
Job complete Thanks Russell McCoy

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405 A	1	PUMP CHARGE 9-18-08 Bottom	625.00	625.00
5406	25	MILEAGE 9-18-08 stay	3.65	91.25
5409	2 hr	Misc Pump 9-20-08	200.00	400.00
5406	25 miles	9-20-08	3.65	91.25
1131	135 SKs	60/40 Pozmix cement	11.35	1,532.25
1118 A	500 #	(Gel For Gel SPACER)	.17	85.00
5526	2 hr	80 Bbl Vac Truck 9-20-08	100.00	200.00
4406	1	5 1/2 Top Rubber Plug	61.00	61.00
0407	5.61 ton	Bulk Truck	m/c	315.00
		Sub TOTAL		3400.75
		SALES TAX		105.13
		ESTIMATED TOTAL		3506.48

Rev 3737

883906

AUTHORIZATION Witnessed by Gale TITLE Co/Rep DATE _____