


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Harvey County, Sec. 6 Twp. 10S Rge. 26W (X) (W)  
Location as "NE/CNW/SW" or footage from lines NE 1/4 NE 1/4 NW 1/4  
Lease Owner Leben Drilling, Inc.  
Lease Name Harvey Well No. 1  
Office Address 905 Central Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 3-4-58 19  
Application for plugging filed 3-4-58 19  
Application for plugging approved 3-4-58 19  
Plugging commenced 3-4-58 19  
Plugging completed 3-4-58 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fabrisious  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	224'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug @ 500' w/25 sacks cement  
2nd plug @ 230' w/15 sacks cement  
Top plug @ 40' w/10 sacks cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 11 1958  
03-11-1958  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Leben Drilling, Inc.  
Address 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
I, Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin  
905 Central Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of March, 19 58

My commission expires June 17, 1961

Ruth N. Benjamin  
Ruth N. Benjamin Notary Public.

PLUGGING  
FILE SEC 6 T 10 R 26 W  
BOOK PAGE 88 LINE 31

15-179-00078-00-00

DRILLER'S LOG

COMPANY:  
CONTRACTOR:  
FARM:  
LOCATION:  
  
COMMENCED:  
COMPLETED:

LEBEN DRILLING, INC.  
LEBEN DRILLING, INC.  
HARVEY #1  
NE 1/4 NE 1/4 NW 1/4 SEC. 6-10S-26W  
SHERIDAN COUNTY, KANSAS  
2-20-58  
3-4-58

0	100	Sand & Shale	
100	162	Post Rock & Shale	
162	225	Blue Shale	
225	500	Shale & Shells	TOPS:
500	1100	Shale	Anhydrite 2285
1100	1285	Shale & Shells	Topeka 3625
1285	1390	Sand	Heebner 3859
1390	1525	Shale & Shells	Lansing K.C. 3897
1525	1910	Lime & Shale	Bs. K. C. 4124
1910	2060	Sand	
2060	2285	Red Bed & Shale	ELEVATION 2668 K. B.
2285	2325	Anhydrite	
2325	2880	Shale & Lime	
2880	3410	Lime & Shale	
3410	3795	Shale & Lime	
3795	3859	Shale & Lime	
3859	3863	Heebner	
3863	3865	Lime & Shale	
3865	3955	Lime & Shale	
3955	4124	Lime	
4124	4150	Base K. C.	
	4150	Rotary Total Depth - Depth	

Set 22 1/2 of 8 5/8" surface casing with 150 sacks cement and 3 sacks CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Harvey #1, located NE 1/4 NE 1/4 NW 1/4 of Section 6, Township 10 South, Range 26 West, Sheridan County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

BY: Frank Hamlin  
Frank Hamlin

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 10th day of March, 1958.

Ruth N. Benjamin  
Ruth N. Benjamin, Notary Public

My Commission Expires:  
June 17, 1961.

MAR 11 1958  
03-11-1958  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 6 T 10 R 26  
BOOK PAGE 88 LINE 31