

6 090292

API NUMBER 15-065-22,290-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE, SEC. 18, T. 10 S., R. 22 W12

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5421

Lease Name Griffith Well # 1

Operator: Sage Drilling Co., Inc.

County S Graham

Name & Address 202 S. St. Francis

Well Total Depth 4200 ^{136.50} feet

Wichita, Ka. 67202

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sage Drilg. Co., Inc. License Number 5421

Address Wichita, Ka. 67202

Company to plug at: Hour: Day: 14 Month: February Year: 19 86

Plugging proposal received from Spencer Hummel

(company name) Sage Drilg. Co., Inc. (phone) 316-263-6139

were: Order 200 sha. 60/40 cement, 6% gel & 8 5/8" wpi plug, spot all plugs through drill pipe w/ heavy mud between all plugs.

Plugging Proposal Received by Edwin A. Schumacher
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 PM, Day: 15 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug 4160' w/ 20 sha.

2nd plug 1930' w/ 20 sha.

3rd plug 1050' w/ 1 sh. Cello-Flake & 100 sha.

4th plug 335' w/ 40 sha.

5th plug 40' solid bridge w/ 10 sha.

10 sha. in rat hole 26
3-1-86

Remarks: Elevation - 2377', Anhydrite - 1920', Arbuschli - 4160'
(If additional description is necessary, use BACK of this form. Wallerburton)

INVOICED
DATE MAR 12 1986 observe this plugging.

Signed Edwin A. Schumacher
(TECHNICIAN)

INV. NO. 12960

MAR 11 1986
03-11-1986
CONSERVATION DIVISION