

6050272

R

API NUMBER 15-06522272-06-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

W. 18 N. SEC. 23, T. 10 S, R. 22 W

3630 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5118  
Operator: T.H.T. Petroleum Corp  
Name & Address: 209 E Millian  
Wichita Kans 67202

Lease Name Watkins Well # 1

County Graham

Well Total Depth 3925 127.56 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 344

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abernombie Drilling Co. License Number 5472

Address Wichita Kans.

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Harold Mailey

(company name) Abernombie (phone) \_\_\_\_\_

Work: Order 215 of 60/40 Poz mix 6% Gel 3% cel @ - 1 sk flo cel  
8 5/8 Plug 1 saw hulls. Circulate hole with heavy mud  
Set all plug thru drill pipe.

Elev 2245 - 1625 = 620 + 300 = 920

Depth 1732 to 75

STATE CORPORATION COMMISSION  
JAN 8 1986  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by \_\_\_\_\_

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_

Operations Completed: Hour: 5:30am Day: 24 Month: 12 Year: 1985

ACTUAL PLUGGING REPORT

1st Plug @ 3870 w/ 20 sk Cemented by Halliburton  
2nd Plug @ 1740 w/ 20 sk  
3rd Plug @ 980 w/ 110 sk 1 saw flo cel  
4th Plug @ 360 w/ 40 sk  
5th Plug @ 40 w/ 8 5/8 Plug 1 saw hulls 10 sk

Remarks: 15 sk in rat hole  
(if additional description is necessary, use BACK of this form.)

INVOICED  
did not observe this plugging.

Signed Gilbert P. Leiker  
(TECHNICIAN)

DATE JAN 14 1986

INV. NO. 12014

12-24

53  
1-6-85  
MS