

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-300 ⁵¹00-00

^{NW} - NE-NE, SEC. 21, T 10S, R24 W/D

15
R

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # _____

_____ FEET FROM N/S SECTION LINE

_____ FEET FROM W/E SECTION LINE

OPERATOR: JOLLY J. INC.
NAME & ADDRESS: BOX 572
RUSSELL, KANSAS.
67665

LEASE NAME CULP WELL # 1

COUNTY GRAHAM

WELL TOTAL DEPTH 4036 \$131.17 FEET

CONDUCTOR PIPE: SIZE 0 FEET

SURFACE CASING: SIZE 8 5/8 FEET 218

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR GEORGE NICHOLAS CSG. LICENSE NUMBER 6698

ADDRESS BOX 373 GENESEO, KANSAS. 67444

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 20th MONTH: JUNE YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM GEORGE NICHOLAS

(COMPANY NAME) NICHOLAS CASING PULLING (PHONE) 316-824-6483

WERE: 8 5/8" - 218 FT SP. CUL, 5 1/2" CSB. SET @ 4034 FT +/- 100 FT.
PLUG. BACK T.D. 3900 FT, PERF'S. 3839 FT TO 3845 FT
AT BOTTOM, 5ST CNT., SAND TO 3780 FT AND 5ST CNT., SHOT-2, REC. 880^{FT.}
ORDERED 165ST 50% Pozmix 6% GEL, 3% CA-CL, 20ST GEL, 5ST HULL'S.
AND 8 5/8" PLUG. PUMP IN WITH PUMP TRUCK.

PLUGGING PROPOSAL RECEIVED BY Marvin Schmidt
(TECHNICIAN) (DOIC)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 20th MONTH: JUNE YEAR: 19 83

ACTUAL PLUGGING REPORT ORDERED 165ST 50% Pozmix 6% GEL, 3% CA-CL.

20ST GEL, 5ST HULL'S. AND 8 5/8" PLUG, PUMPED IN WITH PUMP TRUCK.

PUMPED IN 8 5/8" SP., 4ST HULL'S, 25ST CNT., 10ST GEL, 1/2ST HULL'S.

10ST CNT., 10ST GEL, 1/2ST HULL'S., RELEASED PLUG AND 10ST CNT.

MAX. PRESSURE 300 PSI [CEMENTED BY SUN CNT.]

REMARKS: _____

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1983

CONSERVATION DIVISION
Wichita, Kansas

I (DID / ~~DOES~~) OBSERVE THIS PLUGGING.

SIGNED Marvin Schmidt
(TECHNICIAN) (DOIC)

INVOICED

DATE 7-6-83
INV. NO. 0-4705-W

FORM CP-2/3
REV. 6-83